


23 PATRICK COURT, WATERFORD WEST

8 LOT RESIDENTIAL SUBDIVISION

CIVIL WORKS

DRAWING INDEX

| | |
|-----|--|
| 000 | DRAWING INDEX & LOCALITY PLAN |
| 010 | SAFETY IN DESIGN RISK REGISTER |
| 020 | GENERAL NOTES |
| 030 | EXISTING SITE LAYOUT PLAN |
| 110 | EROSION AND SEDIMENT CONTROL PLAN - PRE START PHASE |
| 120 | EROSION AND SEDIMENT CONTROL PLAN - CONSTRUCTION PHASE |
| 130 | EROSION AND SEDIMENT CONTROL PLAN - NOTES |
| 140 | EROSION AND SEDIMENT CONTROL PLAN - DETAILS SHEET 1 OF 2 |
| 150 | EROSION AND SEDIMENT CONTROL PLAN - DETAILS SHEET 2 OF 2 |
| 200 | EARTHWORKS PLAN |
| 210 | EARTHWORKS SECTIONS |
| 300 | DRIVEWAY SETOUT PLAN |
| 320 | STORMWATER DRAINAGE PLAN |
| 400 | STORMWATER CATCHMENT PLAN |
| 410 | STORMWATER LONGITUDINAL SECTIONS |
| 420 | STORMWATER CALCULATION TABLE |
| 700 | SEWERAGE RETICULATION PLAN |
| 710 | SEWERAGE LONGITUDINAL SECTIONS |
| 800 | WATER RETICULATION PLAN |



LOCALITY PLAN
SCALE 1:1000

| | | | | | | | | | | | | | |
|---------|----------------------|--------|-------|----------|------------------|--------------------|-----------------------------|--|------------------------|---|-------------------------------|-------------|----------|
| REV | REVISION DESCRIPTION | DESIGN | DRAWN | DATE | SCALE | APPROVED | DAVID HOLSTEIN (RPEQ 17025) |  PROJECT MANAGEMENT CIVIL ENGINEERING LAND DEVELOPMENT | CLIENT | PROJECT | DRAWING TITLE | | |
| A | ISSUE FOR APPROVAL | SO | AR | 02.06.21 | 1:1000 1:2000 | | | | STRATEGIC DEVELOPMENTS | 23 PATRICK COURT 23 PATRICK COURT, WATERFORD WEST LOTS 2 ON RP868324, 3 ON RP186717, 900 ON RP233953, 901 ON RP233970, 902 ON RP231480 & 239 ON SP195519 | DRAWING INDEX & LOCALITY PLAN | | |
| COUNCIL | | | | | | LOGAN CITY COUNCIL | | FOR AND ON BEHALF OF CIVIL360 ENGINEERING PTY LTD. THESE DRAWINGS HAVE BEEN PRODUCED FOR THE NOMINATED CLIENTS EXCLUSIVE USE AND ARE THE COPYRIGHT OF CIVIL360 ENGINEERING PTY LTD. THE DRAWING CANNOT BE RELIED UPON BY ANY THIRD PARTY, OR REPRODUCED IN WHOLE OR IN PART, WITHOUT WRITTEN PERMISSION FROM CIVIL360 ENGINEERING PTY LTD. | ASSOCIATED CONSULTANTS | STATUS | PROJECT No. | DRAWING No. | REVISION |
| | | | | | | | | 0406 424 223 / 0423 593 058 info@civil360.com.au | | ISSUE FOR APPROVAL | 2020212 | 000 | A |

SAFETY IN DESIGN / RISK ASSESSMENT REGISTER

| | |
|--------------------------------|----------------------------------|
| PROJECT: | 23 PATRICK COURT, WATERFORD WEST |
| LOCATION: | 23 PATRICK COURT, WATERFORD WEST |
| CIVIL360 PROJECT No. | 2020212 |
| PROJECT DESCRIPTION: | CIVIL OPERATIONAL WORKS PACKAGE |
| RISK REGISTER REVISION: | 1 |
| REVISION DATE: | 27.05.21 |

CONSULTATION WITH PRINCIPAL: 27.05.21

| RISK ID No. | PROJECT PHASE | ACTIVITY / ELEMENT | TYPE OF HAZARD | DESCRIPTION OF HAZARD | LIKELIHOOD | CONSEQUENCE | INITIAL RISK RATING | RISK MANAGER | TREATMENT OPTION/ CONTROL | LIKELIHOOD | CONSEQUENCE | RESIDUAL RISK RATING | COMMENT |
|-------------|---------------|--------------------|-----------------------------------|---|------------|-------------|---------------------|---------------------|--|------------|-------------|----------------------|---------|
| 1 | DESIGN | STORMWATER SYSTEM | EXISTING CONNECTIONS | EXISTING PROPERTIES ARE CONNECTED TO THE STORMWATER SYSTEM | 5 | 3 | 15 | DESIGNER/ENGINEER | INCLUDE NOTES ON DRAWING TO ALERT CONTRACTOR OF CATCHMENTS AND POTENTIAL FLOWS | 5 | 2 | 10 | |
| 2 | DESIGN | STORMWATER SYSTEM | LEVELS BASED ON TRACE LOCATOR | SURVEY LEVELS NOT ACCURATE | 4 | 4 | 16 | DESIGNER/CONTRACTOR | POTHOLE SERVICES PRIOR TO COMMENCEMENT. NOTE ADDED ON DRAWING. | 2 | 4 | 8 | |
| 3 | DESIGN | SEWER RETICULATION | EXISTING CONNECTIONS | EXISTING PROPERTIES ARE CONENCTED TO THE SYSTEM | 5 | 4 | 20 | DESIGNER/ENGINEER | INCLUDE LIVE WORKS CONNECTION TABLE | 5 | 3 | 15 | |
| 4 | DEMOLITION | FENCES | UNCONTROLLED ACCESS TO SITE | ACCESS FROM NEIGHBOURING PROPERTIES INTO WORKS SITE | 5 | 4 | 20 | ALL PARTIES | INCLUDE NOTE ON DRAWING. TEMPORARY FENCE OR NEW FENCE MUST BE INSTALLED IMMEDIATELY AFTER REMOVAL OF EXISTING FENCES | 1 | 4 | 4 | |
| 5 | CONSTRUCTION | CLEARING | SNAKES | BITES FROM VENEMOUS AND NON-VENEMOUS SNAKES | 3 | 5 | 15 | CONTRACTOR | SPOTTER CATCHER TO BE ENGAGED. UNDERTAKE CLEARING IN ONE DIRECTION TO PROVIDE EGRESS FOR SNAKES TO WATERWAY. INCLUDE ON SITE INDUCTION | 2 | 4 | 8 | |
| 6 | CONSTRUCTION | ROADWORKS | TRAFFIC | WORKS NEAR ROAD | 5 | 4 | 20 | CONTRACTOR | TRAFFIC MANAGEMENT PLAN REQUIRED. ENSURE ALL CONSTRUCTION IS UNDERTAKEN IN ACCORDANCE WITH CONTRACTOR SWMS AND PROCEDURES | 1 | 4 | 4 | |
| 7 | CONSTRUCTION | ALL CIVIL WORKS | MOVING OBJECTS | MOBILE PLANT ACTIVE ON SITE DURING CONSTRUCTION | 3 | 5 | 15 | CONTRACTOR | CONTRACTOR TO UNDERTAKE WORK IN ACCORDANCE WITH THEIR SAFE WORK METHOD STATEMENT | 1 | 5 | 5 | |
| 8 | CONSTRUCTION | EARTHWORKS | STEEP GRADES | OVERTURNING OF PLANT | 3 | 4 | 12 | CONTRACTOR | CONTRACTOR TO UNDERTAKE WORK IN ACCORDANCE WITH THEIR SAFE WORK METHOD STATEMENT. ANSURE FENCING IS CONSTRUCTED ALONG ALL BOUNDARIES. | 2 | 4 | 8 | |
| 9 | CONSTRUCTION | EARTHWORKS | SLOPE STABILITY | EMBANKMENT COLLAPSE / LAND SLIP | 3 | 4 | 12 | CONTRACTOR | CONTRACTOR TO UNDERTAKE WORK IN ACCORDANCE WITH THEIR SAFE WORK METHOD STATEMENT | 1 | 4 | 4 | |
| 10 | CONSTRUCTION | SEWER RETICULATION | DEEP EXCAVATION / SLOPE STABILITY | DEEP EXCAVATION / STEEP BATTER FACE DURING CONSTRUCTION | 3 | 3 | 9 | CONTRACTOR | CONTRACTOR TO UNDERTAKE WORK IN ACCORDANCE WITH THEIR SAFE WORK METHOD STATEMENT, INCLUDING BENCHING AND/OR SHORING. | 3 | 2 | 6 | |
| 11 | CONSTRUCTION | SEWER RETICULATION | DEEP EXCAVATION / SLOPE STABILITY | DEEP EXCAVATION ADJACENT LOT 8 | 5 | 5 | 25 | CONTRACTOR | CONTRACTOR TO UNDERTAKE WORK IN ACCORDANCE WITH THEIR SAFE WORK METHOD STATEMENT, INCLUDING BENCHING AND/OR SHORING. | 3 | 2 | 6 | |
| 12 | CONSTRUCTION | STORMWATER SYSTEM | CONFINED SPACES | WORKING WITHIN MANHOLES | 5 | 4 | 20 | CONTRACTOR | ENSURE CONFINED SPACE PERMIT IS IN PLACE AND UNDERAKE IN ACCORDANCE WITH PERMIT REQUIREMENTS AND CODE OF PRACTICE | 5 | 2 | 10 | |
| 13 | CONSTRUCTION | SEWER RETICULATION | CONFINED SPACES | WORKING WITHIN MANHOLES | 5 | 4 | 20 | CONTRACTOR | ENSURE CONFINED SPACE PERMIT IS IN PLACE AND UNDERAKE IN ACCORDANCE WITH PERMIT REQUIREMENTS AND CODE OF PRACTICE | 5 | 2 | 10 | |
| 14 | CONSTRUCTION | ALL CIVIL WORKS | WORKING NEAR LIVE SERVICES | WORKING NEAR LIVE SERVICES | 4 | 5 | 20 | CONTRACTOR | CONSULT DIAL BEFORE YOU DIG, ON-SITE INSPECTION PRIOR TO WORK COMMENCING. DO NOT RELY ON SERVICE NOTED ON DESIGN DRAWINGS OR SURVEY | 1 | 5 | 5 | |
| 15 | CONSTRUCTION | EARTHWORKS | WORKING AT HEIGHTS | >1m HIGH RETAINING WALL ADJACENT LOT 6 PRESENTS A LARGE VERTICAL DROP | 4 | 4 | 16 | CONTRACTOR | FALL PROTECTION REQUIRED DURING CONSTRUCTION. TEMPORARY OR PERMANENT FENCING TO BE INSTALLED WHEN WORKS ARE NOT OCCURRING.. | 1 | 4 | 4 | |
| 16 | MAINTENANCE | BUILDINGS | LIVE SERVICES | DAMAGE TO SERVICES DURING BUILDING WORKS. | 4 | 4 | 16 | DEVELOPER | PROVIDE AS-CONSTRUCTED DRAWINGS TO BUILDERS PRIOR TO COMMENCEMENT. | 2 | 4 | 8 | |
| 17 | REFURBISHMENT | NORMAL USE | NO ATYPICAL RISKS | | | | | | | | | | |
| 18 | DEMOLITION | NORMAL USE | NO ATYPICAL RISKS | | | | | | | | | | |



| | | | | | | | |
|------------------------|----------------|-------|----------|-------|--------|----|----|
| LIKELIHOOD | ALMOST CERTAIN | 5 | 5 | 10 | 15 | 20 | 25 |
| | LIKELY | 4 | 4 | 8 | 12 | 15 | 18 |
| | POSSIBLE | 3 | 3 | 6 | 9 | 12 | 15 |
| | UNLIKELY | 2 | 2 | 4 | 6 | 8 | 10 |
| | RARE | 1 | 1 | 2 | 3 | 4 | 5 |
| | | 1 | 2 | 3 | 4 | 5 | |
| | INSIGNIFICANT | MINOR | MODERATE | MAJOR | SEVERE | | |
| POTENTIAL CONSEQUENCES | | | | | | | |

| POTENTIAL CONSEQUENCES | SCORE |
|---|-------|
| MINOR INJURY OR PHYSICAL DISCOMFORT OR SHORT TERM PSYCHOLOGICAL IMPACT | 1 |
| INJURY OR ILLNESS REQUIRING FIRST AID MEDICAL TREATMENT OR PSYCHOLOGICAL IMPACT REQUIRING SUPPORT | 2 |
| INJURY OR ILLNESS REQUIRING HOSPITAL ADMISSION AND/OR TEMPORARY IMPAIRMENT PSYCHOLOGICAL IMPACT REQUIRING MEDICAL TREATMENT | 3 |
| INJURY OR ILLNESS REQUIRING LONG TERM OR PERMANENT IMPAIRMENT OR RESULTING IN TEMPORARY IMPAIRMENT TO MULTIPLE PEOPLE | 4 |
| INJURY OR ILLNESS RESULTING IN FATALITY OR LONG TERM OR PERMANENT IMPAIRMENT TO MULTIPLE PEOPLE | 5 |



| LIKELIHOOD | SCORE |
|---|-------|
| COULD HAPPEN, BUT PROBABLY NEVER WILL | 1 |
| NOT LIKELY TO OCCUR IN NORMAL CIRCUMSTANCES | 2 |
| MAY OCCUR SOME TIME | 3 |
| EXPECTED TO OCCUR AT SOME TIME | 4 |
| EXPECTED TO OCCUR REGULARLY | 5 |

| RISK RATING | | |
|-------------|-----------|---|
| 1-3 | LOW | NO FURTHER ACTION IS REQUIRED UNLESS BENEFICIAL ACTION CAN BE READILY UNDERTAKEN |
| 4-9 | MEDIUM | CONTROL MEASURES SHOULD BE PUT IS PLACE TO REDUCE RISK UNLESS THERE IS LITTLE BENEFIT |
| 10-16 | HIGH | ALL REASONABLE AND PRACTICABLE CONTROLS MUST BE PUT IN PLACE PRIOR TO UNDERTAKING THIS ACTIVITY |
| 17-25 | VERY HIGH | ACTIVITY MUST NOT OCCUR UNTIL ADDITIONAL CONTROLS HAVE BEEN PUT IN PLACE TO REDUCE RISK TO AN ACCEPTABLE LEVEL. |

| | | | | | | | | | | | | | | | | | |
|-----|----------------------|--------|-------|----------|-------|----------|-----------------------------|---|------------------------|------------------------|---------|---|---------------|--------------------------------|-------------|-----|----------|
| REV | REVISION DESCRIPTION | DESIGN | DRAWN | DATE | SCALE | APPROVED | DAVID HOLSTEIN (RPEQ 17025) |  <p>PROJECT MANAGEMENT CIVIL ENGINEERING LAND DEVELOPMENT</p> <p>0406 424 223 / 0423 593 058 info@civil360.com.au</p> | CLIENT | STRATEGIC DEVELOPMENTS | PROJECT | 23 PATRICK COURT 23 PATRICK COURT, WATERFORD WEST LOTS 2 ON RP868324, 3 ON RP186717, 900 ON RP233953, 901 ON RP233970, 902 ON RP231480 & 239 ON SP195519 | DRAWING TITLE | SAFETY IN DESIGN RISK REGISTER | | | |
| A | ISSUE FOR APPROVAL | SO | AR | 02.06.21 | | | | | ASSOCIATED CONSULTANTS | | STATUS | ISSUE FOR APPROVAL | PROJECT No. | 2020212 | DRAWING No. | 010 | REVISION |
| | | | | | | COUNCIL | LOGAN CITY COUNCIL | <small>FOR AND ON BEHALF OF CIVIL360 ENGINEERING PTY LTD. THESE DRAWINGS HAVE BEEN PRODUCED FOR THE NOMINATED CLIENTS EXCLUSIVE USE AND ARE THE COPYRIGHT OF CIVIL360 ENGINEERING PTY LTD. THE DRAWING CANNOT BE RELIED UPON BY ANY THIRD PARTY, OR REPRODUCED IN WHOLE OR IN PART, WITHOUT WRITTEN PERMISSION FROM CIVIL360 ENGINEERING PTY LTD.</small> | | | | | | | | | |



| | | | | | | | | | | | | | | | | | | | |
|---|--|--|--|---|--|--|--|---|--|---|--|---|--|---|--|---------------------------|--|----------------------|--|
| REV REVISION DESCRIPTION A ISSUE FOR APPROVAL B ADDITIONAL CONNECTION FROM GTP2781 ADDED | | DESIGN/DRAWN DATE SO AR 02.06.21 DH DH 02.09.21 | | SCALE 1:250 5 0 5 10m A1 1:500 A3 | | APPROVED DAVID HOLSTEIN (RPEQ 17025) | | CIVIL 360 ENGINEERING PROJECT MANAGEMENT CIVIL ENGINEERING LAND DEVELOPMENT | | CLIENT STRATEGIC DEVELOPMENTS | | PROJECT 23 PATRICK COURT 23 PATRICK COURT, WATERFORD WEST LOTS 2 ON RP868324, 3 ON RP186717, 900 ON RP233953, 901 ON RP233970, 902 ON RP231480 & 239 ON SP195519 | | DRAWING TITLE EXISTING SITE LAYOUT PLAN | | | | | |
| COUNCIL LOGAN CITY COUNCIL | | | | FOR AND ON BEHALF OF CIVIL360 ENGINEERING PTY LTD. THESE DRAWINGS HAVE BEEN PRODUCED FOR THE NOMINATED CLIENT'S EXCLUSIVE USE AND ARE THE COPYRIGHT OF CIVIL360 ENGINEERING PTY LTD. THE DRAWING CANNOT BE RELIED UPON BY ANY THIRD PARTY, OR REPRODUCED IN WHOLE OR IN PART, WITHOUT WRITTEN PERMISSION FROM CIVIL360 ENGINEERING PTY LTD. | | | | 0406 424 223 / 0423 593 058 info@civil360.com.au | | ASSOCIATED CONSULTANTS | | STATUS ISSUE FOR APPROVAL | | PROJECT No. 2020212 | | DRAWING No. 030 | | REVISION B | |





INSET A
SCALE 1:250

- NOTES: PHASE 1 WORKS**
1. PHASE 1 EROSION AND SEDIMENT CONTROL WORKS HEREIN INVOLVE ALL ACTIVITIES REQUIRED TO BE INSTALLED BY THE CONTRACTOR PRIOR TO COMMENCING WORKS.
 2. STABILISED SITE ACCESS AND SITE FACILITIES ARE TO BE PROVIDED PRIOR TO CONSTRUCTION.
 3. ANY ADDITIONAL SITE ACCESS POINT(S), INCLUDING THROUGH PRIVATE PROPERTY, MUST BE AGREED IN WRITING AND VERIFIED WITH LOGAN CITY COUNCIL AND IN ACCORDANCE WITH ANY CONSTRUCTION MANAGEMENT PLAN.
 4. SITE EXIT POINTS MUST BE APPROPRIATELY MANAGED TO MINIMISE THE RISK OF SEDIMENT BEING TRACKED ONTO SEALED, PUBLIC ROADWAYS. SHAKE DOWN GRID MAY BE REQUIRED WHERE ROCK IS INADEQUATE TO REMOVE MAJORITY OF SOIL FROM VEHICLES.
 5. STORMWATER RUNOFF FROM ACCESS ROADS AND STABILISED ENTRY/EXIT POINTS MUST DRAIN TO AN APPROPRIATE SEDIMENT CONTROL DEVICE.
 6. THE PHASE 1 WORKS INCLUDE:
 - INSTALL SILT FENCE, SITE COMPOUND AND STABILISED ENTRY
 - INSTALL SITE SECURITY FENCING IN ACCORDANCE WITH THE CONTRACTORS SAFETY MANAGEMENT PLAN
 7. REFER TO DWG 2020212-130 FOR ADDITIONAL NOTES AND DETAILS.

LEGEND

| | |
|--|---|
| | LIMIT OF WORKS |
| | DIRECTION OF OVERLAND FLOW |
| | EXISTING SURFACE CONTOUR (0.5m INTERVAL) |
| | SEDIMENT CONTROL - FILTER FENCE |
| | EROSION CONTROL - STABILISED ENTRY |
| | SEDIMENT CONTROL - GULLY PROTECTION - FILTER SOCK |
| | EXISTING SEWER MAIN |
| | EXISTING WATER MAIN |
| | EXISTING STORMWATER DRAINAGE |
| | EXISTING TELSTRA |
| | EXISTING UNDERGROUND ELECTRICITY |

| <table border="1"> <thead> <tr> <th>REV</th> <th>REVISION DESCRIPTION</th> <th>DESIGN</th> <th>DRAWN</th> <th>DATE</th> <th>SCALE</th> </tr> </thead> <tbody> <tr> <td>A</td> <td>ISSUE FOR APPROVAL</td> <td>SO</td> <td>AR</td> <td>02.06.21</td> <td>1:250</td> </tr> <tr> <td>B</td> <td>ADDITIONAL CONNECTION FROM GTP2781 ADDED</td> <td>DH</td> <td>DH</td> <td>02.09.21</td> <td>1:500</td> </tr> </tbody> </table> | REV | REVISION DESCRIPTION | DESIGN | DRAWN | DATE | SCALE | A | ISSUE FOR APPROVAL | SO | AR | 02.06.21 | 1:250 | B | ADDITIONAL CONNECTION FROM GTP2781 ADDED | DH | DH | 02.09.21 | 1:500 | <p>APPROVED</p> <p>DAVID HOLSTEIN (RPEO 17025)</p> <p>PROJECT MANAGEMENT CIVIL ENGINEERING LAND DEVELOPMENT</p> <p>0406 424 223 / 0423 593 058 info@civil360.com.au</p> | <p>CLIENT</p> <p>STRATEGIC DEVELOPMENTS</p> | <p>PROJECT</p> <p>23 PATRICK COURT 23 PATRICK COURT, WATERFORD WEST LOTS 2 ON RP868324, 3 ON RP186717, 900 ON RP233953, 901 ON RP233970, 902 ON RP231480 & 239 ON SP195519</p> | <p>DRAWING TITLE</p> <p>EROSION AND SEDIMENT CONTROL PLAN - PRE START PHASE</p> | <p>COUNCIL</p> <p>LOGAN CITY COUNCIL</p> | <p>FOR AND ON BEHALF OF CIVIL360 ENGINEERING PTY LTD. THESE DRAWINGS HAVE BEEN PRODUCED FOR THE NOMINATED CLIENTS EXCLUSIVE USE AND ARE THE COPYRIGHT OF CIVIL360 ENGINEERING PTY LTD. THE DRAWING CANNOT BE RELIED UPON BY ANY THIRD PARTY, OR REPRODUCED IN WHOLE OR IN PART, WITHOUT WRITTEN PERMISSION FROM CIVIL360 ENGINEERING PTY LTD.</p> | <p>ASSOCIATED CONSULTANTS</p> | <p>STATUS</p> <p>ISSUE FOR APPROVAL</p> | <p>DRAWING No.</p> <p>110</p> | <p>REVISION</p> <p>B</p> |
|---|--|---|-------------------------------|--------------------------|-------|-------|---|--------------------|----|----|----------|-------|---|--|----|----|----------|-------|---|---|--|---|--|---|-------------------------------|---|-------------------------------|--------------------------|
| REV | REVISION DESCRIPTION | DESIGN | DRAWN | DATE | SCALE | | | | | | | | | | | | | | | | | | | | | | | |
| A | ISSUE FOR APPROVAL | SO | AR | 02.06.21 | 1:250 | | | | | | | | | | | | | | | | | | | | | | | |
| B | ADDITIONAL CONNECTION FROM GTP2781 ADDED | DH | DH | 02.09.21 | 1:500 | | | | | | | | | | | | | | | | | | | | | | | |
| <p>PROJECT No.</p> <p>2020212</p> | | <p>STATUS</p> <p>ISSUE FOR APPROVAL</p> | <p>DRAWING No.</p> <p>110</p> | <p>REVISION</p> <p>B</p> | | | | | | | | | | | | | | | | | | | | | | | | |



INSET A
SCALE 1:250

- NOTES: PHASE 2 WORKS**
- DUST CONTROL SHOULD BE UNDERTAKEN USING WATER CARTS AND SOIL BINDERS (IF REQUIRED). LIMIT CONSTRUCTION TRAFFIC DURING PERIODS OF HIGH WINDS AND LIMIT SPEED TO 25km/hr. ONCE EARTHWORKS HAVE BEEN COMPLETED, TOPSOIL SHOULD BE REPLACED AS SOON AS PRACTICABLE. WINDBREAKS (60% SHADE CLOTH) MAY ALSO BE NECESSARY IN LOCALISED SECTIONS TO LIMIT IMPACT ON CLOSE NEIGHBOURS.
 - THE CONTRACTOR SHOULD ASSESS THE REQUIREMENT FOR DUST FENCES BASED ON WEATHER CONDITIONS AND ACTUAL MATERIAL ENCOUNTERED ON SITE. IT IS NOTED THAT EROSION CONTROL MEASURES TO TREAT THE DUST AT THE SOURCE, SUCH AS WATERING, CHEMICAL STABILISATION AND MINIMISING DISTURBANCE IS PREFERABLE THAN UTILISING DUST FENCE AS A MEANS OF SEDIMENT CONTROL.
 - DUST MUST CONTINUE TO BE MONITORED AND ASSESSED DURING THE CONSTRUCTION PERIOD.
 - UTILISE MULCH WON ON SITE IN LIEU OF SEDIMENT FENCES WHERE POSSIBLE.
 - TEST AND AMELIORATE TOPSOIL IN ACCORDANCE WITH CONTRACT SPECIFICATIONS.
 - WHERE GEOFABRIC IS USED TO PROVIDE EROSION CONTROL ON DISTURBED AREAS, ENSURE FABRIC OVERLAPS OUTER EDGES BY 200mm AND BURY 200mm
 - PROVIDE MULCHING, CHEMICAL STABILISERS, SOIL BINDERS OR IMPERVIOUS BLANKETS ON LONG TERM STOCKPILES (>10 DAYS).
 - STABILISE AREAS AS SOON AS PRACTICABLE. 70% COVER WITHIN 30 DAYS (LOW RISK); 70% COVER WITHIN 20 DAYS (MODERATE RISK); 75% COVER WITHIN 10 DAYS (HIGH RISK) OR 80% COVER WITHIN 5 DAYS (EXTREME RISK) OF COMPLETION OF WORKS IN THAT AREA.
 - UTILISE HYDROMULCH OR SEED/POLYMER MIX FOR STABILISATION OF ALLOTMENTS.
 - ANY MATERIAL DROPPED OR TRACKED ONTO A ROAD AS A RESULT OF THE WORKS IS CLEANED UP AS SOON AS PRACTICABLE. WASHING/FLUSHING SHOULD ONLY OCCUR WHERE SWEEPING HAS FAILED TO REMOVE SUFFICIENT SEDIMENT AND THERE IS A COMPELLING NEED TO REMOVE. ALL THE REMAINING SEDIMENT (I.E. SAFETY REQUIREMENT). IN SUCH CIRCUMSTANCES, ALL REASONABLE AND PRACTICABLE SEDIMENT CONTROL MEASURES MUST BE USED TO PREVENT, OR AT LEAST MINIMISE THE RELEASE OF SEDIMENT INTO RECEIVING WATERS WATER TRAPPED IN BASINS SHOULD BE USED ON SITE WHEREVER PRACTICABLE.
 - REFER TO DWG 2020212-130 FOR ADDITIONAL NOTES AND DETAILS.

LEGEND

| | |
|--|---|
| | LIMIT OF WORKS |
| | DIRECTION OF OVERLAND FLOW |
| | EXISTING SURFACE CONTOUR (0.5m INTERVAL) |
| | SEDIMENT CONTROL - FILTER FENCE |
| | EROSION CONTROL - STABILISED ENTRY |
| | SEDIMENT CONTROL - GULLY PROTECTION - FILTER SOCK |
| | PROPOSED SEWER MAIN |
| | PROPOSED STORMWATER |
| | PROPOSED WATER MAIN |
| | AREA OF CUT |
| | AREA OF FILL |
| | EXISTING STORMWATER DRAINAGE |
| | EXISTING WATER MAIN |
| | EXISTING STORMWATER DRAINAGE |

| <table border="1"> <thead> <tr> <th>REV</th> <th>REVISION DESCRIPTION</th> <th>DESIGN</th> <th>DRAWN</th> <th>DATE</th> <th>SCALE</th> </tr> </thead> <tbody> <tr> <td>A</td> <td>ISSUE FOR APPROVAL</td> <td>SO</td> <td>AR</td> <td>02.06.21</td> <td>1:250</td> </tr> <tr> <td>B</td> <td>ADDITIONAL CONNECTION FROM GTP2781 ADDED</td> <td>DH</td> <td>DH</td> <td>02.09.21</td> <td>1:500</td> </tr> </tbody> </table> | REV | REVISION DESCRIPTION | DESIGN | DRAWN | DATE | SCALE | A | ISSUE FOR APPROVAL | SO | AR | 02.06.21 | 1:250 | B | ADDITIONAL CONNECTION FROM GTP2781 ADDED | DH | DH | 02.09.21 | 1:500 | <p>APPROVED</p> <p>DAVID HOLSTEIN (RPEO 17025)</p> <p>PROJECT MANAGEMENT CIVIL ENGINEERING LAND DEVELOPMENT</p> <p>0406 424 223 / 0423 593 058 info@civil360.com.au</p> | <p>CLIENT</p> <p>STRATEGIC DEVELOPMENTS</p> | <p>PROJECT</p> <p>23 PATRICK COURT 23 PATRICK COURT, WATERFORD WEST LOTS 2 ON RP868324, 3 ON RP186717, 900 ON RP233953, 901 ON RP233970, 902 ON RP231480 & 239 ON SP195519</p> | <p>DRAWING TITLE</p> <p>EROSION AND SEDIMENT CONTROL PLAN - CONSTRUCTION PHASE</p> | <p>ASSOCIATED CONSULTANTS</p> | <p>STATUS</p> <p>ISSUE FOR APPROVAL</p> | <p>PROJECT No.</p> <p>2020212</p> | <p>DRAWING No.</p> <p>120</p> | <p>REVISION</p> <p>B</p> |
|---|--|----------------------|--------|----------|-------|-------|---|--------------------|----|----|----------|-------|---|--|----|----|----------|-------|---|---|--|--|-------------------------------|---|-----------------------------------|-------------------------------|--------------------------|
| REV | REVISION DESCRIPTION | DESIGN | DRAWN | DATE | SCALE | | | | | | | | | | | | | | | | | | | | | | |
| A | ISSUE FOR APPROVAL | SO | AR | 02.06.21 | 1:250 | | | | | | | | | | | | | | | | | | | | | | |
| B | ADDITIONAL CONNECTION FROM GTP2781 ADDED | DH | DH | 02.09.21 | 1:500 | | | | | | | | | | | | | | | | | | | | | | |

COUNCIL
LOGAN CITY COUNCIL

FOR AND ON BEHALF OF CIVIL360 ENGINEERING PTY LTD.
THESE DRAWINGS HAVE BEEN PRODUCED FOR THE NOMINATED CLIENTS EXCLUSIVE USE
AND ARE THE COPYRIGHT OF CIVIL360 ENGINEERING PTY LTD. THE DRAWING CANNOT BE
RELIED UPON BY ANY THIRD PARTY, OR REPRODUCED IN WHOLE OR IN PART, WITHOUT
WRITTEN PERMISSION FROM CIVIL360 ENGINEERING PTY LTD.

GENERAL NOTES:

- ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES MUST BE IMPLEMENTED AND A REVISED EROSION AND SEDIMENT CONTROL PLAN (ESCP) MUST BE SUBMITTED FOR APPROVAL IN THE EVENT THAT SITE CONDITIONS CHANGE SIGNIFICANTLY FROM THOSE CONSIDERED WITHIN THE ESCP.
- IN CIRCUMSTANCES WHERE IT IS CONSIDERED NECESSARY TO PREPARE AN AMENDED EROSION AND SEDIMENT CONTROL PLAN (ESCP), AND WHERE THE DELIVERY OF SUCH AN AMENDED ESCP IS NOT IMMINENT, THEN ALL NECESSARY NEW OR MODIFIED EROSION AND SEDIMENT CONTROL WORKS MUST BE IN ACCORDANCE WITH THE *IECA BEST PRACTICE GUIDELINES*. UPON APPROVAL OF THE AMENDED ESCP, ALL WORKS MUST BE IMPLEMENTED IN ACCORDANCE WITH THE AMENDED PLAN.

DISPERSIVE SOILS

- NO RESULTS WERE OBTAINED TO DETERMINE DISPERSIVE SOILS. WHERE DISPERSIVE SOILS ARE ENCOUNTERED DURING CONSTRUCTION THE CONTRACTOR MUST OBTAIN A REVISED K-FACTOR FROM THE GEOTECHNICAL ENGINEER.

SITE MONITORING:

- THE CONTRACTOR WILL IMPLEMENT A MONITORING AND ASSESSMENT PROGRAM ON-SITE TO IDENTIFY, MEASURE, RECORD AND REPORT ON THE EFFECTIVENESS OF THE EROSION AND SEDIMENT CONTROL AND THE FULLNESS OF RELEASES.
- THE CONTRACTOR SHALL IDENTIFY A DEDICATED PERSON TO UNDERTAKE THE MONITORING.
- THE PROGRAM SHALL MONITOR ALL EVENT BASED RELEASES AND RELEASES CAUSED BY THE RAIN EVENTS.
- ALL NON-COMPLIANCES SHALL BE REPORTED TO THE SUPERINTENDENT AND RELEVANT AUTHORITIES (AS APPLICABLE) WITHIN 48 HOURS IDENTIFICATION OF NON-COMPLIANCE.
- WHERE RELEASE CRITERIA ARE EXCEEDED, THE CONTRACTOR WILL IMPLEMENT ADDITIONAL OR ALTERNATE CONTROLS TO ACHIEVE ENVIRONMENTAL OUTCOMES.

SITE MAINTENANCE:

- ALL EROSION AND SEDIMENT CONTROL MEASURES, INCLUDING DRAINAGE CONTROL MEASURES, MUST BE MAINTAINED IN PROPER WORKING ORDER AT ALL TIMES DURING THEIR OPERATIONAL LIVES.
- ALL DRAINAGE, EROSION AND SEDIMENT CONTROL MEASURES MUST BE INSPECTED:
 - AT LEAST DAILY (WHEN WORK IS OCCURRING ON-SITE);
 - AT LEAST WEEKLY (WHEN WORK IS NOT OCCURRING ON-SITE);
 - WITHIN 24 HOURS OF EXPECTED RAINFALL; AND
 - WITHIN 18 HOURS OF A RAINFALL EVENT OF SUFFICIENT INTENSITY AND DURATION TO CAUSE RUNOFF ON-SITE).
- WASHING/FLUSHING OF SEALED ROADWAYS MUST ONLY OCCUR WHERE SWEEPING HAS FAILED TO REMOVE SUFFICIENT SEDIMENT AND THERE IS A COMPELLING NEED TO REMOVE THE REMAINING SEDIMENT (E.G. FOR SAFETY REASONS). IN SUCH CIRCUMSTANCES, ALL REASONABLE AND PRACTICABLE SEDIMENT CONTROL MEASURES MUST BE USED TO PREVENT, OR AT LEAST MINIMISE, THE RELEASE OF SEDIMENT INTO RECEIVING WATERS. ONLY THOSE MEASURES THAT WILL NOT CAUSE SAFETY AND PROPERTY FLOODING ISSUES SHALL BE EMPLOYED. SEDIMENT REMOVED FROM ROADWAYS MUST BE DISPOSED OF IN A LAWFUL MANNER THAT DOES NOT CAUSE ONGOING SOIL EROSION OR ENVIRONMENTAL HARM.
- SEDIMENT REMOVED FROM SEDIMENT TRAPS AND PLACES OF SEDIMENT DEPOSITION MUST BE DISPOSED OF IN A LAWFUL MANNER THAT DOES NOT CAUSE ONGOING SOIL EROSION OR ENVIRONMENTAL HARM.
- MAINTENANCE MOWING OF ALL ROAD SHOULDERS, TABLE DRAINS, BATTERS AND OTHER SURFACES LIKELY TO EXPERIENCE ACCELERATED SOIL EROSION MUST AIM TO LEAVE THE GRASS LENGTH NO SHORTER THAN 50mm WHERE REASONABLE AND PRACTICABLE.
- MAINTENANCE MOWING MUST BE DONE IN A MANNER THAT WILL NOT DAMAGE THE PROFILE OF FORMED, SOFT EDGES, SUCH AS THE CREST OF EARTH EMBANKMENTS.

- ALL OFFICE FACILITIES AND OPERATIONAL ACTIVITIES MUST BE LOCATED SUCH THAT ANY LIQUID EFFLUENT (E.G. PROCESS WATER, WASH-DOWN WATER, EFFLUENT FROM EQUIPMENT CLEANING, OR PLANT WATERING), CAN BE TOTALLY CONTAINED AND TREATED WITHIN THE SITE.
- THE CONSTRUCTION SCHEDULE MUST AIM TO MINIMISE THE DURATION THAT ANY AND ALL AREAS OF SOIL ARE EXPOSED TO THE EROSIIVE EFFECTS OF WIND, RAIN AND SURFACE WATER.
- LAND-DISTURBING ACTIVITIES MUST BE UNDERTAKEN IN ACCORDANCE WITH THE EROSION AND SEDIMENT CONTROL PLAN (ESCP) AND ASSOCIATED DEVELOPMENT CONDITIONS.
- LAND-DISTURBING ACTIVITIES MUST BE UNDERTAKEN IN SUCH A MANNER THAT ALLOWS ALL REASONABLE AND PRACTICABLE MEASURES TO BE UNDERTAKEN TO:
 - ALLOW STORMWATER TO PASS THROUGH THE SITE IN A CONTROLLED MANNER AND AT NON-EROSIVE FLOW VELOCITIES UP TO THE SPECIFIED DESIGN STORM DISCHARGE;
 - MINIMISE SOIL EROSION RESULTING FROM RAIN, WATER FLOW AND/OR WIND;
 - MINIMISE ADVERSE EFFECTS OF SEDIMENT RUNOFF, INCLUDING SAFETY ISSUES;
 - PREVENT, OR AT LEAST MINIMISE, ENVIRONMENTAL HARM RESULTING FROM WORK-RELATED SOIL EROSION AND SEDIMENT RUNOFF;
 - ENSURE THAT THE VALUE AND USE OF LAND/PROPERTIES ADJACENT TO THE DEVELOPMENT (INCLUDING ROADS) ARE NOT DIMINISHED AS A RESULT OF THE ADOPTED ESC MEASURES.
- ALL EROSION AND SEDIMENT CONTROL MEASURES MUST CONFORM TO THE STANDARDS AND SPECIFICATIONS CONTAINED IN:
 - THE DEVELOPMENT APPROVAL CONDITION ISSUED BY THE RELEVANT AUTHORITY; AND
 - THE APPROVED ESCP AND SUPPORTING DOCUMENTATION; OR
 - THE LATEST VERSION OF IECA BEST PRACTICE EROSION AND SEDIMENT CONTROL GUIDELINES IF THE STANDARDS AND SPECIFICATIONS ARE NOT CONTAINED IN THE APPROVED ESCP.
- ADDITIONAL AND/OR ALTERNATIVE ESC MEASURES MUST BE IMPLEMENTED IN THE EVENT THAT SITE INSPECTIONS, THE SITE'S MONITORING AND MAINTENANCE PROGRAM, OR THE REGULATORY AUTHORITY, IDENTIFIES THAT UNACCEPTABLE OFF-SITE SEDIMENTATION IS OCCURRING AS A RESULT OF THE WORK ACTIVITIES.
- LAND-DISTURBING ACTIVITIES MUST NOT CAUSE UNNECESSARY SOIL DISTURBANCE IF AN ALTERNATIVE CONSTRUCTION PROCESS IS AVAILABLE THAT ACHIEVES THE SAME OR EQUIVALENT OUTCOMES AT AN EQUIVALENT COST.
- SEDIMENT (INCLUDING CLAY, SILT, SAND, GRAVEL, SOIL, MUD, CEMENT AND CERAMIC WASTE) DEPOSITED OFF THE SITE AS A DIRECT RESULT OF AN ON-SITE ACTIVITY, MUST BE COLLECTED AND THE AREA APPROPRIATELY CLEANED/REHABILITATED AS SOON AS REASONABLE AND PRACTICABLE, AND IN A MANNER THAT GIVES APPROPRIATE CONSIDERATION TO THE SAFETY AND ENVIRONMENTAL RISKS ASSOCIATED WITH THE SEDIMENT DEPOSITION.
- WHEREVER REASONABLE AND PRACTICABLE, BRICK, TILE AND MASONRY CUTTING MUST BE CARRIED OUT ON A PERVIOUS SURFACE, SUCH AS GRASS, OR OPEN SOIL. OR IN SUCH A MANNER THAT ALL SEDIMENT-LADEN RUNOFF IS PREVENTED FROM DISCHARGING INTO A GUTTER, DRAIN, OR WATER BODY.
- ADEQUATE WASTE COLLECTION BINS MUST BE PROVIDED ON-SITE AND MAINTAINED SUCH THAT POTENTIAL AND ACTUAL ENVIRONMENTAL HARM RESULTING FROM SUCH MATERIAL WASTE IS MINIMISED.
- CONCRETE WASTE AND CHEMICAL PRODUCTS, INCLUDING PETROLEUM AND OIL-BASED PRODUCTS, MUST BE PREVENTED FROM ENTERING AN INTERNAL WATER BODY, OR AN EXTERNAL DRAIN, STORMWATER SYSTEM, OR WATER BODY.
- ALL FLAMMABLE AND COMBUSTIBLE LIQUIDS, INCLUDING ALL LIQUID CHEMICALS IF SUCH CHEMICALS COULD POTENTIALLY BE WASHED OR DISCHARGED FROM THE SITE, ARE STORED AND HANDLED ON-SITE IN ACCORDANCE WITH RELEVANT STANDARDS SUCH AS AS1940 *THE STORAGE AND HANDLING OF FLAMMABLE AND COMBUSTIBLE LIQUIDS*.
- TRENCHES NOT LOCATED WITHIN ROADWAYS MUST BE BACKFILLED, CAPPED WITH TOPSOIL, AND COMPACTED TO A LEVEL AT LEAST 75mm ABOVE ADJOINING GROUND LEVEL AND APPROPRIATELY STABILISED.
- ALL STORMWATER, SEWER LINE AND OTHER SERVICE TRENCHES, NOT LOCATED WITHIN ROADWAYS, MUST BE MULCHED AND SEEDED, OTHER OTHERWISE APPROPRIATELY STABILISED WITHIN 7 DAYS AFTER BACKFILL.
- NO MORE THAN 150m OF A STORMWATER, SEWER LINE OR OTHER SERVICE TRENCH MUST BE OPEN AT ANY ONE TIME.
- SITE SPOIL MUST BE LAWFULLY DISPOSED OF IN A MANNER THAT DOES NOT RESULT IN ONGOING SOIL EROSION OR ENVIRONMENTAL HARM.

EROSION CONTROL RECOMMENDATIONS

- ENTRY AND EXIT POINTS, AND SITE FACILITIES (INCLUDING PARKING) MUST BE STABILISED AS EARLY AS POSSIBLE.
- THE SITE HAS BEEN CLEARED PREVIOUSLY FOR THE CONSTRUCTION OF A RESIDENTIAL DWELLING. CLEARING OF TREES IS LIMITED.
- STABILISE SOIL STOCKPILES AND UNFINISHED EARTHWORKS IF RAINFALL IS REASONABLY ANTICIPATED, AND WHERE DISTURBANCE IS EXPECTED TO BE SUSPENDED FOR A PERIOD EXCEEDING 20 DAYS DURING 'LOW - MEDIUM' EROSION RISK MONTHS AND 10 DAYS DURING 'HIGH' EROSION RISK MONTHS
- STAGED CONSTRUCTION AND STABILISATION OF EARTH BATTERS (STEEPER THAN 1:6) IN MINIMUM 3m VERTICAL INCREMENTS WHEREVER REASONABLE AND PRACTICABLE.
- RETAIN ANY MULCH (WON FROM TREE CLEARING) ON SITE FOR EROSION CONTROL DURING CONSTRUCTION (< 10% SLOPES).
- STABILISE DISTURBED SOIL SURFACES WITH MINIMUM 75% COVER WITHIN 20 DAYS OF COMPLETION OF WORKS WITHIN ANY AREA OF THE WORK SITE. THIS CAN BE ACHIEVED USING MULCH IN ACCORDANCE WITH THE PREVIOUS DOT POINT. DURING CIVIL WORKS, THE CONTRACTOR MAY NEED TO USE POLYMER STABILISERS FOR THIS PURPOSE.
- USE HEAVY MULCHING ON AREAS EXPECTED TO BE EXPOSED FOR LONG PERIODS OF TIME (>12 MONTHS). TYPES OF HEAVY MULCHING INCLUDE BARK OR WOODCHIP MULCH, COMPOST BLANKETS AND ROCK MULCH. POLYMER STABILISERS MAY ALSO BE USED WITH CAUTION.
- WATER CARTS ARE TO BE UTILISED AS DUST CONTROL ON THIS SITE.
- LOOSE ORGANIC MULCH MAY BE UTILISED ON SLOPES UP TO 1 IN 4 EXCEPT WHERE CONCENTRATED FLOWS ARE EXPECTED DOWN THE SLOPE. SLOPES STEEPER THAN 1 IN 4 WILL REQUIRE EROSION CONTROL BLANKETS (OR OTHER APPROVED EROSION CONTROL MEASURE) PRIOR TO REVEGETATION. UPSTREAM DIVERSION DRAINS OR BUNDS, LINED CHUTES OR SLOPE DRAINS SHOULD ALSO BE CONSIDERED WHERE RAIN IS IMMINENT TO REDUCE EROSION ON EXPOSED SLOPES.

DRAINAGE CONTROL RECOMMENDATIONS

- IT IS RECOMMENDED THAT THE MAXIMUM SPACING OF DIRTY WATER CATCH DRAINS OR DIVERSION CHANNELS WITH BANKS FOR THIS PROJECT BE 20m.
- WHERE SLOPES ARE PROTECTED BY SUITABLE EROSION CONTROL METHODS (SUCH AS EROSION CONTROL BLANKETS, BONDED FIBRE MATRIX OR A HYDROMULCH STABILISED WITH A NON RE-WETTABLE TACKIFIER), CATCH DRAINS (OR DIVERSION BANKS) CAN BE OMITTED.
- WHERE DIRTY WATER CATCH DRAINS ARE NOT LINED, THE VELOCITY WITHIN THESE DRAINS IS TO BE LIMITED TO 0.5m/s USING CHECK DAMS. SAND BAG CHECK DAMS ARE APPROPRIATE IN DRAINS LESS THAN 500mm DEEP AND WHERE THE GRADIENT IS LESS THAN 10%.
- DRAINAGE CONTROLS HAVE BEEN SIZED IN ACCORDANCE WITH THE STATE PLANNING POLICY. TEMPORARY DRAINAGE STRUCTURES ARE EXPECTED TO HAVE DESIGN LIFE <12 MONTHS AND HAVE BEEN DESIGNED FOR 1 IN 2 YEAR ARI/39% AEP.

EROSION RISK

| LOCATION | | JAN | FEB | MAR | APR | MAY | JUN | JUL | AUG | SEP | OCT | NOV | DEC | ANNUAL |
|-----------------------------------|--------------------------|------|------|------|----------|----------|----------|-----|-----|-----|----------|----------|------|--------|
| MONTHLY RAINFALL | s: | 581 | 594 | 444 | 248 | 154 | 138 | 96 | 68 | 68 | 167 | 260 | 392 | 3209 |
| | e: -27.6792 e: 153.12 | HIGH | HIGH | HIGH | MODERATE | MODERATE | MODERATE | LOW | LOW | LOW | MODERATE | MODERATE | HIGH | |
| 23 PATRICK STREET, WATERFORD WEST | | | | | | | | | | | | | | |

EROSION CONTROL:

- ALL EROSION CONTROL MEASURES MUST BE APPLIED AND MAINTAINED IN ACCORDANCE WITH IECA BEST PRACTICE EROSION AND SEDIMENT CONTROL GUIDELINES
- WHERE PRACTICABLE, MULCHED VEGETATION CAN BE UTILISED FOR EROSION CONTROL.
- THE APPLICATION OF LIQUID-BASED DUST SUPPRESSION MEASURES MUST ENSURE THAT SEDIMENT-LADEN RUNOFF RESULTING FROM SUCH MEASURES DOES NOT CREATE A TRAFFIC OR ENVIRONMENTAL HAZARD.
- ALL TEMPORARY EARTH BANKS, FLOW DIVERSION SYSTEMS, AND EMBANKMENTS ASSOCIATED WITH CONSTRUCTED SEDIMENT BASINS MUST BE MACHINE-COMPACTED, SEEDED AND MULCHED FOR THE PURPOSE OF ESTABLISHING A TEMPORARY VEGETATIVE COVER WITHIN 10 DAYS AFTER GRADING.
- THE CONSTRUCTION AND STABILISATION OF EARTH BATTERS STEEPER THAN 6:1 (H:V) MUST BE STAGED SUCH THAT NO MORE THAN 3 VERTICAL-METRES OF ANY BATTER IS EXPOSED TO RAINFALL AT ANY INSTANT.
- SYNTHETIC REINFORCED EROSION CONTROL MATS AND BLANKETS MUST NOT BE PLACED WITHIN, OR ADJACENT TO, RIPARIAN ZONES AND WATERCOURSES IF SUCH MATERIALS ARE LIKELY TO CAUSE ENVIRONMENTAL HARM TO WILDLIFE OR WILDLIFE HABITATS.
- A MINIMUM 60% GROUND COVER MUST BE ACHIEVED ON ALL NON-COMPLETED EARTHWORKS EXPOSED TO ACCELERATED SOIL EROSION IF FURTHER CONSTRUCTION ACTIVITIES OR SOIL DISTURBANCES ARE LIKELY TO BE SUSPENDED FOR MORE THAN 30 DAYS DURING THOSE MONTHS WHEN THE RISK RATING IS LESS THAN 'VERY LOW'; MINIMUM 70% COVER WITHIN 30 DAYS IF RISK RATING IS 'LOW'; MINIMUM 70% COVER WITHIN 20 DAYS IF RISK RATING IS 'MEDIUM'; MINIMUM 75% COVER WITHIN 10 DAYS IF RISK RATING IS 'HIGH'; AND MINIMUM 80% COVER WITHIN 5 DAYS IF RISK RATING IS 'EXTREME'.

SEDIMENT CONTROL:

- ALL SEDIMENT CONTROL MEASURES MUST BE APPLIED AND MAINTAINED IN ACCORDANCE WITH IECA BEST PRACTICE EROSION AND SEDIMENT CONTROL GUIDELINES
- OPTIMUM BENEFIT MUST BE MADE OF EVERY OPPORTUNITY TO TRAP SEDIMENT WITHIN THE WORK SITE, AND AS CLOSE AS PRACTICABLE TO ITS SOURCE.
- SEDIMENT TRAPS MUST BE INSTALLED AND OPERATED TO BOTH COLLECT AND RETAIN SEDIMENT.
- THE POTENTIAL SAFETY RISK OF A PROPOSED SEDIMENT TRAP TO SITE WORKERS AND THE PUBLIC MUST BE GIVEN APPROPRIATE CONSIDERATION, ESPECIALLY THOSE DEVICES LOCATED WITHIN PUBLICLY ACCESSIBLE AREAS.
- ALL REASONABLE AND PRACTICABLE MEASURES MUST BE TAKEN TO PREVENT, OR AT LEAST MINIMISE, THE RELEASE OF SEDIMENT FROM THE SITE.
- SUITABLE ALL-WEATHER MAINTENANCE ACCESS MUST BE PROVIDED TO ALL SEDIMENT CONTROL DEVICES.
- SEDIMENT CONTROL DEVICES MUST BE DE-SILTED AND MADE FULLY OPERATIONAL AS SOON AS REASONABLE AND PRACTICABLE AFTER A SEDIMENT-PRODUCING EVENT, WHETHER NATURAL OR ARTIFICIAL, IF THE DEVICE'S SEDIMENT RETENTION CAPACITY FALLS BELOW 75% OF ITS DESIGN RETENTION CAPACITY.
- MATERIALS, WHETHER LIQUID OR SOLID, REMOVED FROM SEDIMENT CONTROL DEVICES DURING MAINTENANCE OR DECOMMISSIONING, MUST BE DISPOSED OF IN A MANNER THAT DOES NOT CAUSE ONGOING SOIL EROSION OR ENVIRONMENTAL HARM.

DISCHARGE LIMITS

TOTAL SUSPENDED SOLIDS (TSS) = 50mg/L AS A MAXIMUM CONCENTRATION
 TUBIDITY (NTU) LESS THAN 10% ABOVE BACKGROUND
 pH BETWEEN 6.5 AND 8.5 (EXCEPT WHERE RECEIVING WATERS LAY OUTSIDE THIS RANGE)

TSS RELEASE MAY EXCEED 50mg/L WHERE:

- FURTHER SIGNIFICANT RAINFALL IS FORECAST TO OCCUR BEFORE THE TSS CONCENTRATION IS LIKELY TO BE REDUCED TO 50MG/L;
- RELEASING A HIGHER CONCENTRATION OF TOTAL SUSPENDED SOLIDS WILL RESULT IN A BETTER ENVIRONMENTAL OUTCOME BY PROVIDING STORAGE FOR THE CAPTURE AND TREATMENT OF RUN-OFF FROM THE IMMINENT RAINFALL AND RUN-OFF;
- ALL REASONABLE AND PRACTICABLE STEPS HAVE BEEN TAKEN TO TREAT THE WATER WITHIN BEST-PRACTICE TIME FRAMES;
- FLOCCULENT HAS BEEN APPROPRIATELY APPLIED AND THE CONCENTRATION OF TSS IN THE CAPTURED WATER HAS ALREADY SIGNIFICANTLY DECREASED.

FOR ALL OTHER STORMWATER RELEASES, FLOWS AND DISCHARGES FROM THE SITE, THE RELEASE LIMITS PRESCRIBED ABOVE MUST NOT BE EXCEEDED UNLESS THE DEVELOPMENT IS IN FULL COMPLIANCE WITH THIS STANDARD

SOIL LOSS ESTIMATION - RUSLE

A = R.K.L.S.C.P
 R = 2453
 K = 0.044 (CLAYEY SANDS)
 LS = 0.31 (2% MAX SLOPE / 40m max)
 C = 1.0 (CONSTRUCTION SITE)
 P = 1.3 (COMPACTED AND SMOOTH)

A = 2453 x 0.044 x 0.31 x 1.0 x 1.3 = 57 t/ha/yr
 BASED ON ANNUAL SOIL LOSS AND AREA OF DISTURBANCE, TYPE III SEDIMENT CONTROLS ARE APPROPRIATE.
 PRIORITY SHOULD BE GIVEN TO EROSION CONTROL (STABILISE FINISHED WORKS).

DRAINAGE CONTROL:

- ALL DRAINAGE CONTROL MEASURES MUST BE APPLIED AND MAINTAINED IN ACCORDANCE WITH IECA BEST PRACTICE EROSION AND SEDIMENT CONTROL GUIDELINES
- WHEREVER REASONABLE AND PRACTICABLE, STORMWATER RUNOFF ENTERING THE SITE FROM EXTERNAL AREAS, AND NON-SEDIMENT LADEN (CLEAN) STORMWATER RUNOFF ENTERING A WORK AREA OR AREA OF SOIL DISTURBANCE, MUST BE DIVERTED AROUND OR THROUGH THAT AREA IN A MANNER THAT MINIMISES SOIL EROSION AND THE CONTAMINATION OF THAT WATER FOR ALL DISCHARGES UP TO THE SPECIFIED DESIGN STORM DISCHARGE.
- DURING THE CONSTRUCTION PERIOD, ALL REASONABLE AND PRACTICABLE MEASURES MUST BE IMPLEMENTED TO CONTROL FLOW VELOCITIES IN SUCH A MANNER THAN PREVENTS SOIL EROSION ALONG DRAINAGE PATHS AND AT THE ENTRANCE AND EXIT OF ALL DRAINS AND DRAINAGE PIPES DURING ALL STORMS UP TO THE RELEVANT DESIGN STORM DISCHARGE.
- TO THE MAXIMUM DEGREE REASONABLE AND PRACTICABLE, ALL WATERS DISCHARGED DURING THE CONSTRUCTION PHASE MUST DISCHARGE ONTO STABLE LAND, IN A NON-EROSIVE MANNER, AND AT A LEGAL POINT OF DISCHARGE.
- WHEREVER REASONABLE AND PRACTICABLE, "CLEAN" SURFACE WATERS MUST BE DIVERTED AWAY FROM SEDIMENT CONTROL DEVICES AND ANY UNTREATED, SEDIMENT-LADEN WATERS.
- DURING THE CONSTRUCTION PERIOD, ROOF WATER MUST BE MANAGED IN A MANNER THAT MINIMISES SOIL EROSION THROUGHOUT THE SITE, AND SITE WETNESS WITHIN ACTIVE WORK AREAS.



| | | | | | | | | | | | | | | |
|-----|----------------------|--------|-------|----------|-------|----------|-----------------------------|---|------------------------|------------------------|---|---|-------------|----------|
| REV | REVISION DESCRIPTION | DESIGN | DRAWN | DATE | SCALE | APPROVED | DAVID HOLSTEIN (RPEO 17025) |  | CLIENT | STRATEGIC DEVELOPMENTS | PROJECT | DRAWING TITLE | | |
| A | ISSUE FOR APPROVAL | SO | AR | 02.06.21 | | | | | | | 23 PATRICK COURT 23 PATRICK COURT, WATERFORD WEST LOTS 2 ON RP868324, 3 ON RP186717, 900 ON RP233953, 901 ON RP233970, 902 ON RP231480 & 239 ON SP195519 | EROSION AND SEDIMENT CONTROL PLAN - NOTES | | |
| | | | | | | | | | ASSOCIATED CONSULTANTS | | STATUS | PROJECT No. | DRAWING No. | REVISION |
| | | | | | | COUNCIL | LOGAN CITY COUNCIL | FOR AND ON BEHALF OF CIVIL360 ENGINEERING PTY LTD. THESE DRAWINGS HAVE BEEN PRODUCED FOR THE NOMINATED CLIENTS EXCLUSIVE USE AND ARE THE COPYRIGHT OF CIVIL360 ENGINEERING PTY LTD. THE DRAWING CANNOT BE RELIED UPON BY ANY THIRD PARTY, OR REPRODUCED IN WHOLE OR IN PART, WITHOUT WRITTEN PERMISSION FROM CIVIL360 ENGINEERING PTY LTD. | | | ISSUE FOR APPROVAL | 2020212 | 130 | A |

LEGEND

- 18.0 — DESIGN SURFACE CONTOURS
- + 17.95 FINISHED SURFACE LEVEL
- - - 60.0 - - - EXISTING SURFACE CONTOURS
- RETAINING WALL
- - - - - LIMIT OF WORKS
- AREA OF CUT
- AREA OF FILL
- - - SW - - - EXISTING STORMWATER DRAINAGE
- - - S - - - EXISTING SEWER
- - - W - - - EXISTING WATER
- - - - - EXISTING FENCE

NOTES:


1. REFER TO DRAWING 020 FOR EARTHWORK NOTES
2. DESIGN CONTOURS SHOWN ON THE DRAWING ARE FINISHED SURFACE LEVELS.




LOT 6 CONCRETE SLEEPER RETAINING WALL

NTS
SLEEPER WALL DESIGN AND CONSTRUCTION TO BE CERTIFIED BY A STRUCTURAL ENGINEER. SUBSOIL DRAINS TO DISCHARGE TO DEDICATED KERB ADAPTOR OR STORMWATER STRUCTURES VIA SOLID uPVC.

| | | | | | | | |
|-----|--|--|-------|---|-------|---|-----------------------------|
| REV | REVISION DESCRIPTION | DESIGN | DRAWN | DATE | SCALE | APPROVED | DAVID HOLSTEIN (RPEO 17025) |
| A | ISSUE FOR APPROVAL | SO | AR | 02.06.21 | 1:200 | | |
| B | ADDITIONAL CONNECTION FROM GTP2781 ADDED | DH | DH | 02.09.21 | 1:400 | | |
| | | | | | | | |
| | | COUNCIL | | LOGAN CITY COUNCIL | | FOR AND ON BEHALF OF CIVIL360 ENGINEERING PTY LTD. THESE DRAWINGS HAVE BEEN PRODUCED FOR THE NOMINATED CLIENTS EXCLUSIVE USE AND ARE THE COPYRIGHT OF CIVIL360 ENGINEERING PTY LTD. THE DRAWING CANNOT BE RELIED UPON BY ANY THIRD PARTY, OR REPRODUCED IN WHOLE OR IN PART, WITHOUT WRITTEN PERMISSION FROM CIVIL360 ENGINEERING PTY LTD. | |
| | | | | PROJECT MANAGEMENT CIVIL ENGINEERING LAND DEVELOPMENT | | CLIENT STRATEGIC DEVELOPMENTS | |
| | | PROJECT 23 PATRICK COURT 23 PATRICK COURT, WATERFORD WEST LOTS 2 ON RP868324, 3 ON RP186717, 900 ON RP233953, 901 ON RP233970, 902 ON RP231480 & 239 ON SP195519 | | DRAWING TITLE EARTHWORKS PLAN | | PROJECT No. 2020212 | |
| | | STATUS ISSUE FOR APPROVAL | | DRAWING No. 200 | | REVISION B | |



SECTION A
SCALE 1:100



SECTION B
SCALE 1:100

| | | | | | | | | | | | | |
|----------|--|--------------|-------------|--------------------|-------------------------|---|--|----------------------------------|--|--------------------------------------|--------------------|---------------|
| REV A | REVISION DESCRIPTION ISSUE FOR APPROVAL | DESIGN SO | DRAWN AR | DATE 02.06.21 | SCALE 1:100 1:200 | APPROVED DAVID HOLSTEIN (RPEQ 17025) | CIVIL 360 ENGINEERING PROJECT MANAGEMENT CIVIL ENGINEERING LAND DEVELOPMENT 0406 424 223 / 0423 593 058 info@civil360.com.au | CLIENT STRATEGIC DEVELOPMENTS | PROJECT 23 PATRICK COURT 23 PATRICK COURT, WATERFORD WEST LOTS 2 ON RP868324, 3 ON RP186717, 900 ON RP233953, 901 ON RP233970, 902 ON RP231480 & 239 ON SP195519 | DRAWING TITLE EARTHWORKS SECTIONS | | |
| | | | | | A1 A3 | FOR AND ON BEHALF OF CIVIL360 ENGINEERING PTY LTD. THESE DRAWINGS HAVE BEEN PRODUCED FOR THE NOMINATED CLIENTS EXCLUSIVE USE AND ARE THE COPYRIGHT OF CIVIL360 ENGINEERING PTY LTD. THE DRAWING CANNOT BE RELIED UPON BY ANY THIRD PARTY, OR REPRODUCED IN WHOLE OR IN PART, WITHOUT WRITTEN PERMISSION FROM CIVIL360 ENGINEERING PTY LTD. | | ASSOCIATED CONSULTANTS | STATUS ISSUE FOR APPROVAL | PROJECT No. 2020212 | DRAWING No. 210 | REVISION A |
| | | COUNCIL | | LOGAN CITY COUNCIL | | | | | | | | |



PATRICK COURT

NOTE:


1. NOMINATED LEVELS ARE EDGE OF CONCRETE (UNLESS NOTED OTHERWISE) AND ARE EQUAL DISTANT.
2. ALL KERB RADII AND KERB SETOUT ARE TO EDGE OF CONCRETE
3. DRIVEWAY MIN 175mm THICK N32 CONCRETE WITH SL72 MESH 50 TOP COVER ON 100mm CBR 15 TYPE 2.5 MATERIAL.
4. VEHICLE CROSSING TYPE A IN ACCORDANCE WITH IPWEA STANDARD DRAWING RS-051.
5. BIN PADS 0.9m x 0.9m 125mm THICK N32 CONCRETE WITH SL72 MESH 50 TOP COVER.

LEGEND


- SW — PROPOSED STORMWATER
- T — PROPOSED DRIVEWAY 175mm
- S — PROPOSED BINPAD 125mm
- R10.27 CURVE RADIUS TO EDGE
- x14.48 LIP LEVEL / SURFACE LEVEL
- x20 SETOUT POINT
- CONCRETE SAW JOINT (SJ)
- CONCRETE EXPANSION JOINT (EJ)
- SW --- EXISTING STORMWATER DRAINAGE
- T --- EXISTING TELSTRA
- S --- EXISTING SEWER
- W --- EXISTING WATER
- OE --- EXISTING OVERHEAD ELECTRICITY
- EXISTING FENCE

SETOUT POINTS


| POINT | EASTING | NORTHING |
|-------|------------|-------------|
| 01 | 511672.916 | 6938278.845 |
| 02 | 511682.100 | 6938279.827 |
| 03 | 511697.141 | 6938275.759 |
| 04 | 511704.328 | 6938275.375 |
| 05 | 511718.234 | 6938277.583 |
| 06 | 511719.431 | 6938277.676 |
| 07 | 511734.935 | 6938277.633 |
| 08 | 511750.440 | 6938277.589 |
| 09 | 511756.599 | 6938274.339 |
| 10 | 511763.488 | 6938264.322 |
| 11 | 511770.083 | 6938260.124 |
| 12 | 511786.484 | 6938257.389 |
| 13 | 511802.885 | 6938254.654 |
| 14 | 511805.828 | 6938256.201 |
| 15 | 511808.740 | 6938262.423 |
| 16 | 511811.652 | 6938268.645 |
| 17 | 511813.669 | 6938271.050 |
| 18 | 511823.644 | 6938277.218 |
| 19 | 511824.786 | 6938278.502 |
| 20 | 511829.525 | 6938288.676 |
| 21 | 511834.265 | 6938298.849 |
| 22 | 511837.437 | 6938297.371 |
| 23 | 511832.698 | 6938287.198 |
| 24 | 511827.958 | 6938277.024 |
| 25 | 511825.485 | 6938274.241 |
| 26 | 511818.779 | 6938270.095 |
| 27 | 511817.628 | 6938268.380 |
| 28 | 511816.164 | 6938259.602 |
| 29 | 511814.700 | 6938250.823 |
| 30 | 511815.862 | 6938248.279 |
| 31 | 511819.734 | 6938245.913 |
| 32 | 511817.908 | 6938242.927 |
| 33 | 511810.366 | 6938247.536 |
| 34 | 511808.938 | 6938248.069 |
| 35 | 511794.917 | 6938250.407 |
| 36 | 511780.852 | 6938252.753 |
| 37 | 511766.875 | 6938255.084 |
| 38 | 511760.280 | 6938259.281 |
| 39 | 511754.443 | 6938267.768 |
| 40 | 511746.231 | 6938272.101 |
| 41 | 511732.743 | 6938272.139 |
| 42 | 511719.255 | 6938272.176 |
| 43 | 511705.194 | 6938269.944 |
| 44 | 511695.708 | 6938270.450 |
| 45 | 511680.664 | 6938274.517 |
| 46 | 511675.442 | 6938273.959 |
| 47 | 511765.555 | 6938258.092 |
| 48 | 511802.432 | 6938251.942 |
| 49 | 511810.580 | 6938255.409 |
| 50 | 511814.997 | 6938269.323 |
| 51 | 511824.501 | 6938275.690 |




JOINT FILLING TYPE 'A'
NTS




NARROW CORNER REINFORCEMENT
NTS



EXPANSION JOINT DETAIL - E.J.
NTS



DOWLLED JOINT- JOINTED REINFORCED PAVEMENT
NTS



SAWCUT JOINT CONCRETE - S.J.
NTS

| REV | REVISION DESCRIPTION | DESIGN | DRAWN | DATE | SCALE |
|-----|---------------------------|--------|-------|----------|-------|
| A | ISSUE FOR APPROVAL | SO | AR | 02.06.21 | 1:250 |
| B | CONVEX MIRRORS NOTE ADDED | SO | AR | 02.07.21 | 1:500 |

LOGAN CITY COUNCIL

APPROVED DAVID HOLSTEIN (RPEO 17025)

FOR AND ON BEHALF OF CIVIL360 ENGINEERING PTY LTD.
THESE DRAWINGS HAVE BEEN PRODUCED FOR THE NOMINATED CLIENTS EXCLUSIVE USE AND ARE THE COPYRIGHT OF CIVIL360 ENGINEERING PTY LTD. THE DRAWING CANNOT BE RELIED UPON BY ANY THIRD PARTY, OR REPRODUCED IN WHOLE OR IN PART, WITHOUT WRITTEN PERMISSION FROM CIVIL360 ENGINEERING PTY LTD.

CIVIL 360 ENGINEERING

PROJECT MANAGEMENT
CIVIL ENGINEERING
LAND DEVELOPMENT

0406 424 223 / 0423 593 058
info@civil360.com.au



CLIENT
STRATEGIC DEVELOPMENTS

ASSOCIATED CONSULTANTS

PROJECT
23 PATRICK COURT
23 PATRICK COURT, WATERFORD WEST
LOTS 2 ON RP868324, 3 ON RP186717, 900 ON RP233953,
901 ON RP233970, 902 ON RP231480 & 239 ON SP195519

STATUS
ISSUE FOR APPROVAL

| DRAWING TITLE | PROJECT No. | DRAWING No. | REVISION |
|-----------------------------|-------------|-------------|----------|
| DRIVEWAY SETOUT PLAN | 2020212 | 300 | B |



LEGEND

- 18.0 ——— DESIGN SURFACE CONTOURS
- SWD ——— PROPOSED STORMWATER LINE
- 2/1 ——— MANHOLE 2 ON LINE 1
- ——— PROPERTY BOUNDARY
- ——— LIMIT OF WORKS
- ——— PROPOSED EASEMENT
- ——— ADJACENT BOUNDARY
- 50 ——— EXISTING SURFACE CONTOURS (0.5m INTERVALS)
- SWD ——— EXISTING STORMWATER
- SWD ——— EXISTING STORMWATER REMOVE
- S ——— EXISTING SEWER MAIN
- S ——— EXISTING SEWER MAIN REMOVE
- W ——— EXISTING WATER MAIN
- T ——— EXISTING TELSTRA
- E ——— EXISTING ELECTRICAL
- ——— EXISTING FENCE
- ——— EXISTING KERB

| REV | REVISION DESCRIPTION | DESIGN | DRAWN | DATE | SCALE |
|-----|--|--------|-------|----------|-------|
| A | ISSUE FOR APPROVAL | SO | AR | 02.06.21 | 1:250 |
| B | ADDITIONAL CONNECTION FROM GTP2781 ADDED | DH | DH | 02.09.21 | 1:500 |

COUNCIL
LOGAN CITY COUNCIL

APPROVED
DAVID HOLSTEIN (RPEQ 17025)

FOR AND ON BEHALF OF CIVIL360 ENGINEERING PTY LTD.
THESE DRAWINGS HAVE BEEN PRODUCED FOR THE NOMINATED CLIENT'S EXCLUSIVE USE AND ARE THE COPYRIGHT OF CIVIL360 ENGINEERING PTY LTD. THE DRAWING CANNOT BE RELIED UPON BY ANY THIRD PARTY, OR REPRODUCED IN WHOLE OR IN PART, WITHOUT WRITTEN PERMISSION FROM CIVIL360 ENGINEERING PTY LTD.

CIVIL 360 ENGINEERING

PROJECT MANAGEMENT
CIVIL ENGINEERING
LAND DEVELOPMENT


0406 424 223 / 0423 593 058
info@civil360.com.au

CLIENT
STRATEGIC DEVELOPMENTS

PROJECT
23 PATRICK COURT
23 PATRICK COURT, WATERFORD WEST
LOTS 2 ON RP868324, 3 ON RP186717, 900 ON RP233953,
901 ON RP233970, 902 ON RP231480 & 239 ON SP195519

STATUS
ISSUE FOR APPROVAL

| DRAWING TITLE | | PROJECT No. | DRAWING No. | REVISION |
|---------------------------------|--|-------------|-------------|----------|
| STORMWATER DRAINAGE PLAN | | 2020212 | 320 | B |



| REV | REVISION DESCRIPTION | DESIGN | DRAWN | DATE | SCALE |
|-----|----------------------|--------|-------|----------|-----------------|
| A | ISSUE FOR APPROVAL | SO | AR | 02.06.21 | 1:500 1:1000 |

SCALE
1:500
1:1000

5 0 5 10 15 20 25m

COUNCIL
LOGAN CITY COUNCIL

APPROVED
DAVID HOLSTEIN (RPEO 17025)

FOR AND ON BEHALF OF CIVIL360 ENGINEERING PTY LTD.
THESE DRAWINGS HAVE BEEN PRODUCED FOR THE NOMINATED CLIENTS EXCLUSIVE USE
AND ARE THE COPYRIGHT OF CIVIL360 ENGINEERING PTY LTD. THE DRAWING CANNOT BE
RELIED UPON BY ANY THIRD PARTY, OR REPRODUCED IN WHOLE OR IN PART, WITHOUT
WRITTEN PERMISSION FROM CIVIL360 ENGINEERING PTY LTD.

CIVIL 360 ENGINEERING

PROJECT MANAGEMENT
CIVIL ENGINEERING
LAND DEVELOPMENT

0406 424 223 / 0423 593 058
info@civil360.com.au

CLIENT
STRATEGIC DEVELOPMENTS


ASSOCIATED CONSULTANTS

PROJECT
23 PATRICK COURT
23 PATRICK COURT, WATERFORD WEST
LOTS 2 ON RP868324, 3 ON RP186717, 900 ON RP233953,
901 ON RP233970, 902 ON RP231480 & 239 ON SP195519

STATUS
ISSUE FOR APPROVAL

| DRAWING TITLE | | PROJECT No. | DRAWING No. | REVISION |
|----------------------------------|--|-------------|-------------|----------|
| STORMWATER CATCHMENT PLAN | | 2020212 | 400 | A |

| |
|-----------------------|
| STRUCTURE NAME |
| STRUCTURE DESCRIPTION |



PIPE SIZE (CLASS)
 PIPE GRADE %
 1 IN
 PIPE LENGTH

| | | | | | | | | | |
|---------------------------------|-----------------------------|-----------------------------|-----------------------------|-----------------------------|-----------------------------|-----------------------------|-----------------------------|-----------------------------|-----------------------------|
| HYDRAULIC GRADELINE | 18.424 | 17.909 | 16.893 | 16.836 | 15.854 | 15.006 | 14.229 | 14.110 | 13.450 |
| PIPE FLOW (Cumecs) | | 0.557 | 0.723 | | 1.156 | | 1.192 | | |
| PIPE CAPACITY AT GRADE (Cumecs) | | 1.797 | 1.969 | | 2.389 | | 2.389 | | |
| DEPTH TO INVERT | | 2.777 | 1.955 | 1.985 | 2.371 | 3.394 | 3.368 | 3.369 | 3.298 |
| INVERT LEVEL | | 17.053 | 15.910 | 15.880 | 15.273 | 14.250 | 13.152 | 13.151 | 10.500 |
| FINISHED SURFACE LEVEL | 19.830 | | 17.865 | 17.644 | 17.644 | 16.520 | 16.520 | 13.798 | 13.798 |
| DISTANCE ALONG DRAINLINE | 0.000 | | 45.724 | 65.964 | 90.798 | 150.776 | | | |
| STRUCTURE LOCATION | E511851.684 N6938223.454 | E511812.671 N6938247.300 | E511812.253 N6938267.536 | E511798.238 N6938288.038 | E511812.253 N6938267.536 | E511830.491 N6938279.447 | E511814.998 N6938269.324 | E511812.253 N6938267.536 | E511762.964 N6938267.257 |

LINE






1

EX375

EX525

3

EX450



| REV | REVISION DESCRIPTION | DESIGN | DRAWN | DATE | SCALE | APPROVED |
|-----|----------------------|--------|-------|----------|--|-----------------------------|
| A | ISSUE FOR APPROVAL | SO | AR | 02.06.21 | 1: 100 VERT. 1: 200 VERT. 1: 1000 HORIZ. 1: 2000 HORIZ. | DAVID HOLSTEIN (RPEO 17025) |

| | |
|---------|--------------------|
| COUNCIL | LOGAN CITY COUNCIL |
|---------|--------------------|

FOR AND ON BEHALF OF CIVIL360 ENGINEERING PTY LTD.
 THESE DRAWINGS HAVE BEEN PRODUCED FOR THE NOMINATED CLIENTS EXCLUSIVE USE AND ARE THE COPYRIGHT OF CIVIL360 ENGINEERING PTY LTD. THE DRAWING CANNOT BE REPRODUCED BY ANY THIRD PARTY, OR REPRODUCED IN WHOLE OR IN PART, WITHOUT WRITTEN PERMISSION FROM CIVIL360 ENGINEERING PTY LTD.

CIVIL 360 ENGINEERING
 PROJECT MANAGEMENT
 CIVIL ENGINEERING
 LAND DEVELOPMENT
 0406 424 223 / 0423 593 058
 info@civil360.com.au

CLIENT
STRATEGIC DEVELOPMENTS
 ASSOCIATED CONSULTANTS

PROJECT
 23 PATRICK COURT
 23 PATRICK COURT, WATERFORD WEST
 LOTS 2 ON RP68324, 3 ON RP186717, 900 ON RP233953,
 901 ON RP233970, 902 ON RP231480 & 239 ON SP195519
 STATUS
ISSUE FOR APPROVAL

| | | | |
|---------------|----------------------------------|-------------|-----|
| DRAWING TITLE | STORMWATER LONGITUDINAL SECTIONS | | |
| PROJECT No. | 2020212 | DRAWING No. | 410 |
| REVISION | A | | |

LIVE SEWER WORKS TABLE

| No. | DESCRIPTION | DIA SEWER | MH NO. | MH/MS TYPE | COVER TYPE | LOT NO. | F.S.L. | E.S.L. | ILL. | DEPTH TO INVERT |
|------|--|-----------|--------|------------|------------|---------|--------|--------|-------|-----------------|
| 1(A) | CONTRACTOR LAY AWAY FROM MANHOLE INSTALLING ALL UPSTREAM SEWER. LEAVE 2.0m GAP. | 150 | 1/S1 | EX | D | 1 | 14.88 | 14.88 | 12.73 | 2.13 |
| 1(B) | ONCE SEWER WORKS ARE SUCCESSFULLY ACCEPTED 'ON MAINTENANCE' LOGAN WATER TO MAKE FINAL CONNECTION, REMOVE EXISTING REDUNDANT CONNECTION AND MAKE GOOD | | | | | | | | | |
| 2(A) | CONTRACTOR LAY AWAY FROM MANHOLE INSTALLING ALL DOWNSTREAM SEWER. LEAVE 2.0m GAP. | 150 | 4/S2 | EX | D | 1 | 19.91 | 19.91 | 18.58 | 1.33 |
| 2(B) | ONCE SEWER WORKS ARE SUCCESSFULLY ACCEPTED 'ON MAINTENANCE' LOGAN WATER TO MAKE FINAL CONNECTION, REMOVE EXISTING REDUNDANT CONNECTION AND MAKE GOOD | | | | | | | | | |




EXISTING SEWER PROPERTY CONNECTION LINES TO REMAIN LIVE UNTIL SEWER ACCEPTED ON MAINTENANCE. WORKS TO BE CARRIED OUT BY A LICENCED PLUMBER UPON COUNCIL APPROVAL FOR A PLUMBING AND DRAINAGE APPLICATION

GENERAL NOTES:

- ALL WORK AND MATERIALS SHALL BE IN ACCORDANCE WITH CURRENT SOUTH EAST QUEENSLAND SEWERAGE CODE SPECIFICATIONS AND STANDARDS.
- UNLESS SPECIFIED OTHERWISE ALL MATERIALS AND WORK SHALL COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS.
- THE CONSTRUCTION OF THE SEWERAGE WORK SHOWN ON THIS DRAWING SHALL BE SUPERVISED BY AN ENGINEER WHO HAS RPQ REGISTRATION. SEWERAGE WORKS NOT COMPLYING WITH THIS REQUIREMENT WILL NOT BE PERMITTED TO CONNECT INTO THE SEQ SERVICE PROVIDER SEWERAGE SYSTEM.
- ALL WORK ASSOCIATED WITH LIVE SEWERS OR MAINTENANCE HOLES SHALL BE CARRIED OUT BY THE SEQ SERVICE PROVIDER AT THE DEVELOPER'S COST.
- ALL PIPES AND MATERIALS SHALL COMPLY WITH THE REQUIREMENTS OF THE 'ACCEPTED PRODUCTS AND MATERIALS' LIST.
- PROPERTY CONNECTIONS SHALL BE LOCATED WITHIN THE PROPERTY AS SHOWN IN THE DRAWINGS.
- PROPERTY CONNECTION BRANCHES SHALL EXTEND INTO THE PROPERTY A MINIMUM OF 300mm AND A MAXIMUM OF 750mm.
- WHERE PIPES ARE LAID IN FILL, THE FILLING SHALL BE CARRIED OUT IN LAYERS NOT EXCEEDING 300mm (LOOSE) IN DEPTH AND SHALL BE COMPACTED UNTIL THE COMPACTION IS NOT LESS THAN 95% OF THE MATERIALS MAXIMUM COMPACTION WHEN TESTED IN ACCORDANCE WITH A.S. 1289 (MODIFIED COMPACTION). TESTING SHALL BE CARRIED OUT AFTER EACH ALTERNATE LAYER. IN ALL SUCH CASES APPROVAL OF CONSTRUCTED SEWERS WILL NOT BE ISSUED BY THE SEQ SERVICE PROVIDER UNLESS CERTIFICATES ARE PRODUCED CERTIFYING THAT THE REQUIRED COMPACTION HAS BEEN ACHIEVED.
- THE CONTRACTOR SHALL VERIFY THE LOCATION AND DEPTH OF EXISTING SERVICES WITH RELEVANT AUTHORITIES BEFORE COMMENCING WORKS.
- SEWERS SHALL BE DISUSED / ABANDONED IN ACCORDANCE WITH PROCEDURES SET OUT IN THE SEQ SEWER CODE.
- BENCH MARK AND LEVELS TO AHD.
- EXISTING ALLOTMENTS REQUIRING A PROPERTY CONNECTION FROM EXISTING SEWERS SHALL BE PROVIDED BY THE SEQ SERVICE PROVIDER AT THE DEVELOPER'S COST.

LEGEND

- 62.0 DESIGN SURFACE CONTOURS
- PROPOSED NOMINAL KERB LINE
- PROPOSED SEWERAGE MANHOLE 1 ON LINE 2
- PROPOSED WATER
- PROPOSED STORMWATER
- RETAINING WALL
- SERVICE EASEMENT
- EXISTING STORMWATER DRAINAGE
- EXISTING STORMWATER REMOVE
- EXISTING SEWER MAIN
- EXISTING SEWER MAIN REMOVE
- EXISTING TELSTRA
- EXISTING SEWER
- EXISTING WATER




SEWERAGE NOTES:

- GENERAL ALIGNMENT OF SEWER PIPES SHALL BE (UNLESS NOTED OTHERWISE):
1.75m OUTSIDE THE PROPERTY BOUNDARIES.
2.30m OUTSIDE THE PROPERTY BOUNDARIES WHEN ADJACENT WATER RETICULATION PIPES.
2.00m FROM REAR BOUNDARIES WHEN ADJACENT TO ROOFWATER DRAINAGE.
- MINIMUM PIPE COVER SHALL BE IN ACCORDANCE WITH CURRENT SOUTH EAST QUEENSLAND (SEQ) SEWERAGE CODE AS FOLLOWS:
PRIVATE PROPERTY NOT SUBJECT TO VEHICULAR LOADING 0.60m
PRIVATE PROPERTY SUBJECT TO VEHICULAR LOADING 0.75m
SEALED ROADS, FOOTWAYS, VERGES, INDUSTRIAL PROPERTY 0.90m
UNSEALED ROADS, ARTERIAL AND FUTURE ROADS 1.20m
- ALL SEWER PIPES SHALL BE uPVC SN8 UNLESS SHOWN OTHERWISE.
- TYPE P2 PRECAST MANHOLES WITH CONVERSION SLABS ARE PREFERRED, SUBJECT TO APPROVAL. REFER SEQ-SEW STD DWG SEQ-SEW-1300-1. CONSTRUCTION MAY INCLUDE A COMBINATION OF PRECAST AND IN-SITU MANHOLES TO SUIT APPLICATION.
- EACH ALLOTMENT SHALL BE SERVICED BY A DN100 PVC DIAMETER PROPERTY CONNECTION. FOR ALLOTMENTS OTHER THAN SINGLE RESIDENTIAL, A DN150 PVC PROPERTY CONNECTION SHALL BE PROVIDED IN ACCORDANCE WITH CURRENT SEQ CODE STANDARDS.
- WHERE SEWERS HAVE A GRADE OF 1 IN 20 OR STEEPER, BULKHEADS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE SEQ SEWER CODE TABLE 9.1 AND STD DWG SEQ-SEW-1206-1.
- PIPE EMBEDMENT AND TRENCHFILL TO BE IN ACCORDANCE WITH SEQ SEWER CODE SEQ-SEW-1200 SERIES STANDARD DRAWINGS, TYPE 3 SUPPORT EMBEDMENT.
- THE INVERT LEVELS SHOWN ON THE LONGITUDINAL SECTIONS ARE THE LEVELS CALCULATED AT THE CENTRES OF MANHOLES.
- HOUSE CONNECTION JUNCTION CHAINAGES SHOWN ON THE LONGITUDINAL SECTIONS ARE MEASURED FROM THE DOWNSTREAM MANHOLE.
- THE LEVELS ON MANHOLE COVERS SHOWN ON THE LONGITUDINAL SECTIONS ARE APPROXIMATE ONLY. THE CONTRACTOR SHALL FINISH MANHOLE COVERS AND SURROUNDS TO SUIT THE SLOPE AND LEVEL OF THE FINISHED SURFACE AT THAT LOCATION UNLESS OTHERWISE DIRECTED BY THE SUPERINTENDENT.
- ALL SEWERS, HOUSE CONNECTIONS, MANHOLES AND BACKFILLING SHALL BE TESTED IN ACCORDANCE WITH SEQ CODE SEWER SPECIFICATIONS.
- DETECTABLE MARKER TAPE TO BE INSTALLED ON ALL NON-METALLIC PIPELINES.
- NO STEP IRONS OR LADDERS TO BE INSTALLED IN SEWER MANHOLES.
- CCTV FOOTAGE TO THE REQUIREMENTS OF LOCAL AUTHORITY TO BE PROVIDED.
- WHERE INTERNAL DROPS ARE CONSTRUCTED, PENETRATIONS INTO THE MANHOLE WALL IS TO BE CONSTRUCTED IN ACCORDANCE WITH SEQ WATER SERVICE PROVIDERS STD DWG SEQ-SEW-1303-1.
- ANY WORKS CONSTRUCTED OUTSIDE OF SPECIFIED TOLERANCES SHALL BE RECTIFIED AT THE CONTRACTORS EXPENSE (IF ORDERED).

| | | | | | | | | | | | | | | | |
|---------|---|--------|-------|----------|-------|--------------------|-----------------------------|---|---|------------------------|------------------------|---------|---|-----------------|----------------------------|
| REV | REVISION DESCRIPTION | DESIGN | DRAWN | DATE | SCALE | APPROVED | DAVID HOLSTEIN (RPEQ 17025) | CIVIL 360 ENGINEERING | PROJECT MANAGEMENT CIVIL ENGINEERING LAND DEVELOPMENT | CLIENT | STRATEGIC DEVELOPMENTS | PROJECT | 23 PATRICK COURT 23 PATRICK COURT, WATERFORD WEST LOTS 2 ON RP868324, 3 ON RP186717, 900 ON RP233953, 901 ON RP233970, 902 ON RP231480 & 239 ON SP195519 | DRAWING TITLE | SEWERAGE RETICULATION PLAN |
| A | ISSUE FOR APPROVAL | SO | AR | 02.06.21 | 1:250 | | | | | | | | | | |
| B | LINE 2 STRUCTURE NUMBERING AMENDED | SO | DH | 02.07.21 | 1:500 | | | | | | | | | | |
| C | ADDITIONAL CONNECTION FROM GTP2781 ADDED | DH | DH | 02.09.21 | | | | | | | | | | | |
| D | CONNECTION FROM GTP2356 AND MH 7/S1 AMENDED | DH | DH | 09.09.21 | | | | | | | | | | | |
| COUNCIL | | | | | | LOGAN CITY COUNCIL | | FOR AND ON BEHALF OF CIVIL360 ENGINEERING PTY LTD. THESE DRAWINGS HAVE BEEN PRODUCED FOR THE NOMINATED CLIENTS EXCLUSIVE USE AND ARE THE COPYRIGHT OF CIVIL360 ENGINEERING PTY LTD. THE DRAWING CANNOT BE RELIED UPON BY ANY THIRD PARTY, OR REPRODUCED IN WHOLE OR IN PART, WITHOUT WRITTEN PERMISSION FROM CIVIL360 ENGINEERING PTY LTD. | | ASSOCIATED CONSULTANTS | | STATUS | | PROJECT No. | |
| | | | | | | | | 0406 424 223 / 0423 593 058 info@civil360.com.au | | ISSUE FOR APPROVAL | | 2020212 | | DRAWING No. 700 | |
| | | | | | | | | | | | | | | REVISION D | |



| |
|-------------------------------|
| STRUCTURE NAME |
| SETOUT CO ORDINATES |
| MANHOLE TYPE |
| LID TYPE |
| JUNCTION LINE |
| DROP TYPE |
| DEPTH TO HC |
| HOUSE CONNECTION INVERT LEVEL |
| HC TYPE |
| HC LOT No |
| CH. FROM D/S MH |

LEGEND



| |
|-----------------------|
| LOCATION |
| DIAMETER |
| EMBEDMENT TYPE |
| GRADE |
| JUNCTION INVERT LEVEL |
| DEPTH TO INVERT |
| INVERT LEVEL OF SEWER |
| DESIGN SURFACE LEVEL |
| RUNNING CHAINAGE |

LINE



SEWER STRUCTURE COVER

| | |
|---|---|
| B | NON-TRAFFICABLE COVER. REFER TO SEQ STD. DRGS SEQ-SEW-1308-8 TO SEQ-SEW-1308-11 |
| D | TRAFFICABLE COVER. REFER TO SEQ STD. DRGS SEQ-SEW-1308-5 TO SEQ-SEW-1308-7 |

SEWER STRUCTURE TYPES

| | |
|------|--|
| 1050 | 1050mm DIA. MAINTENANCE STRUCTURE. REFER TO SEQ STD. DRGS SEQ-1300-1, SEQ-1307-1, SEQ-1308-1 |
| MS | MAINTENANCE SHAFT. TYPE 'J'-1 DN600 POOPIT REFER TO SEQ STD. DRG SEW-1314-1 & 1314-2 |
| RE | RODDING END. REFER TO SEQ STD DRG. SEW-1314-1 |
| END | RUBBER RING SEAL SCREWED CAP FITTING WELDED INTO SEWER PIPELINE. |
| BEND | IN-LINE 3.0m LONG RADIUS PVC SN8 FORMED BEND. REFER TO SEQ-SEW-1314-3 |
| EXMH | EXISTING SEWER MANHOLE |


SEWER STRUCTURE DROPS

| | |
|---|---|
| V | STRAIGHT THROUGH SEWER TYPE 'V'. REFER TO SEQ STD. DRG SEW-1303-1 |
| W | OBLIQUE BACKDROP. REFER TO SEQ STD. DRG SEW-1303-1 |
| X | INTERNAL BACKDROP TYPE 'X'. REFER TO SEQ STD. DRG SEW-1303-1 |
| Y | EXTERNAL BACKDROP TYPE 'Y'. REFER TO SEQ STD. DRG SEW-1303-1 |
| Z | INLET INTO MAINTENANCE SHAFT RISER (MIN 750mm ABOVE DSIL). REFER TO SEQ STD. DRG SEW-1314-1 |

SEWER PROPERTY CONNECTION TYPES

| | |
|----|--|
| A | SEWERAGE HOUSE CONNECTION (STANDARD AND EXTENDED) TYPE 'A'. REFER TO SEQ STD. DRG SEW-1104-1 |
| B | SEWERAGE HOUSE CONNECTION (SLOPED CONNECTION) TYPE 'B'. REFER TO SEQ STD. DRG SEW-1104-1 |
| D | SEWERAGE HOUSE CONNECTION (VERTICAL RISER) TYPE 'D'. REFER TO SEQ STD. DRG SEW-1105-1 |
| V | SEWERAGE HOUSE CONNECTION (STANDARD AND EXTENDED) TYPE 'V'. REFER TO SEQ STD. DRG SEW-1303-1 |
| W | SEWERAGE HOUSE CONNECTION (SLOPED CONNECTION) TYPE 'W'. REFER TO SEQ STD. DRG SEW-1303-1 |
| X | SEWERAGE HOUSE CONNECTION (INTERNAL VERTICAL RISER) TYPE 'X'. REFER TO SEQ STD. DRG SEW-1303-1 |
| Z | INLET INTO MAINTENANCE SHAFT RISER (MIN 750mm ABOVE DSIL). REFER TO SEQ STD. DRG SEW-1314-1 |
| JU | JUMP UP SEWERAGE HOUSE CONNECTION. REFER TO DETAIL. |

- NOTES:**
- HC LEVELS REFER TO IL AT END OF HC. NOTWITHSTANDING HC LEVELS DESIGNED, CONTRACTOR TO ENSURE HC L.O LEVEL IS LOCATED BETWEEN 600mm & 1500mm BELOW FSL.
 - PROVIDE TRENCHSTOPS AS PER SEQ WATER STD DWG SEW-1206-1



| <table border="1"> <tr><th>REV</th><th>REVISION DESCRIPTION</th><th>DESIGN</th><th>DRAWN</th><th>DATE</th><th>SCALE</th></tr> <tr><td>A</td><td>ISSUE FOR APPROVAL</td><td>SO</td><td>AR</td><td>02/06/21</td><td>1:100 VERT.</td></tr> <tr><td>B</td><td>ADDITIONAL CONNECTION FROM GTP2781 ADDED</td><td>DH</td><td>DH</td><td>02/09/21</td><td>1:200 VERT.</td></tr> <tr><td>C</td><td>CONNECTION FROM GTP2356 AND MH 7/S1 AMENDED</td><td>DH</td><td>DH</td><td>09/09/21</td><td></td></tr> </table> | REV | REVISION DESCRIPTION | DESIGN | DRAWN | DATE | SCALE | A | ISSUE FOR APPROVAL | SO | AR | 02/06/21 | 1:100 VERT. | B | ADDITIONAL CONNECTION FROM GTP2781 ADDED | DH | DH | 02/09/21 | 1:200 VERT. | C | CONNECTION FROM GTP2356 AND MH 7/S1 AMENDED | DH | DH | 09/09/21 | | <p>APPROVED</p> <p>DAVID HOLSTEIN (RPEQ 17025)</p> <p>CIVIL 360 ENGINEERING</p> <p>PROJECT MANAGEMENT CIVIL ENGINEERING LAND DEVELOPMENT</p> <p>CLIENT STRATEGIC DEVELOPMENTS</p> <p>PROJECT 23 PATRICK COURT 23 PATRICK COURT, WATERFORD WEST LOTS 2 ON RP868324, 3 ON RP186717, 900 ON RP233953, 901 ON RP233970, 902 ON RP231480 & 239 ON SP195519</p> <p>DRAWING TITLE SEWERAGE LONGITUDINAL SECTIONS</p> | <p>FOR AND ON BEHALF OF CIVIL360 ENGINEERING PTY LTD. THESE DRAWINGS HAVE BEEN PRODUCED FOR THE NOMINATED CLIENTS EXCLUSIVE USE AND ARE THE COPYRIGHT OF CIVIL360 ENGINEERING PTY LTD. THE DRAWING CANNOT BE RELIED UPON BY ANY THIRD PARTY, OR REPRODUCED IN WHOLE OR IN PART, WITHOUT WRITTEN PERMISSION FROM CIVIL360 ENGINEERING PTY LTD.</p> <p>0406 424 223 / 0423 593 058 info@civil360.com.au</p> | <p>ASSOCIATED CONSULTANTS</p> <p>STATUS ISSUE FOR APPROVAL</p> <p>PROJECT No. 2020212</p> <p>DRAWING No. 710</p> <p>REVISION C</p> |
|--|---|----------------------|--------|----------|-------------|-------|---|--------------------|----|----|----------|-------------|---|--|----|----|----------|-------------|---|---|----|----|----------|--|---|---|---|
| REV | REVISION DESCRIPTION | DESIGN | DRAWN | DATE | SCALE | | | | | | | | | | | | | | | | | | | | | | |
| A | ISSUE FOR APPROVAL | SO | AR | 02/06/21 | 1:100 VERT. | | | | | | | | | | | | | | | | | | | | | | |
| B | ADDITIONAL CONNECTION FROM GTP2781 ADDED | DH | DH | 02/09/21 | 1:200 VERT. | | | | | | | | | | | | | | | | | | | | | | |
| C | CONNECTION FROM GTP2356 AND MH 7/S1 AMENDED | DH | DH | 09/09/21 | | | | | | | | | | | | | | | | | | | | | | | |

LEGEND

| | |
|--|---|
| | PROPOSED 100mm DI CL WATER MAIN |
| | FIRE HYDRANT AND SLUICE VALVE |
| | PROPOSED WATER SERVICE (PRIVATE) |
| | PROPOSED WATER METER SERVICE PER SEQ-WAT-1110-1/2 INCLUDING BALL VALVE AND METER BOX (ONLY) |
| | PROPOSED SEWER |
| | PROPOSED STORMWATER |
| | PROPOSED EASEMENT |
| | EXISTING STORMWATER DRAINAGE |
| | EXISTING TELSTRA |
| | EXISTING SEWER |
| | EXISTING WATER |

MINIMUM COVER TO WATER MAINS

| LOCATION | ≤Ø200mm NB | ≥Ø200mm NB |
|------------------------|------------|------------|
| NON ROADWAY | 600mm | 1000mm |
| SEALED ROADS | 600mm | 1000mm |
| MAJOR ROADS/EMBANKMENT | 750mm | 1000mm |
| FREEWAYS | 1200mm | 1200mm |




WATER NOTES:

- THE GENERAL ALIGNMENT OF WATER MAINS SHALL BE 1.50m OUTSIDE THE PROPERTY BOUNDARY UNLESS SHOWN OTHERWISE. WHERE WATER AND SEWER SERVICES SHARE THE SAME VERGE THE WATER ALIGNMENT MAY BE REDUCED FROM 1.5m TO 1.425m.
- WATER RETICULATION MAINS SHALL BE CONSTRUCTED WITH DI CL PN35 PIPE UNLESS SHOWN OTHERWISE.
- TRENCH EMBEDMENT TO BE TYPE C SUPPORT IN ACCORDANCE WITH SEQ CODE STANDARD DRAWING SEQ-WAT-1201-1.
- ALL VALVE AND HYDRANT BOXES TO BE TRAFFICABLE. REFER TO SEQ-WAT-1305-1.
- REFER TO SEQ CODE STANDARD DRAWINGS SEQ-WAT-1301-1 & SEQ-WAT-1302-1 FOR VALVE AND HYDRANT INSTALLATION DETAILS.
- MARKERS ARE REQUIRED FOR ALL HYDRANTS AND VALVES IN ACCORDANCE WITH SEQ CODE STANDARD DRAWINGS SEQ-WAT-1300-1 & SEQ-WAT-1300-2.
- WHERE THERE IS A DIRECT LINE CLASH BETWEEN THE POWER SUPPLY PILLAR/STREET LIGHT AND FIRE HYDRANT THE FIRE HYDRANT IS TO BE LOCATED 1000mm OFF THE PROLONGATION OF ANY COMMON BOUNDARY, i.e. 1000mm AWAY FROM THE POWER SUPPLY PILLAR/STREET LIGHT.
- THE CONTRACTOR SHALL DETERMINE ALLOWABLE BEARING CAPACITIES OF THE UNDISTURBED SIDE OF THE TRENCH. DIMENSIONS OF THE THRUST BLOCK ARE TO BE IN ACCORDANCE WITH SEQ CODE STANDARD DRAWING SEQ-WAT-1205-1.
- WATER MAINS SHALL BE TESTED UNDER HYDRAULIC PRESSURE TO A PRESSURE TEST OF 1.2MPa. REFER TO SEQ CODE AND WSA 03 2011 V3.1 CLAUSE 19.4 FOR DETAILS.
- ALL CONNECTIONS TO EXISTING LIVE WATER MAINS TO BE MADE BY COUNCIL AT DEVELOPER'S EXPENSE. CONNECTION TO INCLUDE STOP VALVE AS DIRECTED BY SUPERINTENDENT.
- WATER SERVICE CONDUITS TO BE 100mm DIA uPVC WITH SOLVENT WELD JOINTS IN ACCORDANCE WITH SEQ CODE STANDARD DRAWING SEQ-WAT-1107-2.
- CONTRACTOR TO SUPPLY BALL VALVE AND METER BOX ONLY. METERS TO BE PROVIDED AND INSTALLED BY LOGAN WATER. PROPERTY CONNECTION SHALL BE PROVIDED IN ACCORDANCE WITH SEQ STANDARD DRAWINGS SEQ-WAT-1110-1-A AND SEQ-WAT-1110-2-A.
- ALL WATER CONDUITS TO EXTEND 300mm BEYOND CONCRETE FOOTPATH IN ACCORDANCE WITH SEQ CODE STANDARD DRAWING SEQ-WAT-1108-1. WHERE NO FOOTPATHS ARE PRESENT, WATER SERVICE CONDUITS ARE TO EXTEND 300mm MINIMUM BEHIND BACK OF KERB.
- ALL HYDRANT TEES ARE TO BE DN100.
- NEW WATER MAIN IN THE VICINITY OF THE LIVE CONNECTION IS TO BE LAID AT A LEVEL THAT SUITS THE EXISTING WATER MAIN.
- CONSTRUCT ALL WATER MAINS, ASSOCIATED STRUCTURES AND APPURTENANCES IN ACCORDANCE WITH THE TOLERANCES SPECIFIED IN CLAUSE 21.2 TO 21.5 INCLUSIVE, EXCEPT WHERE WATER MAINS CROSS OR RUN PARALLEL WITH OTHER SERVICES WHEN MINIMUM CLEARANCES SHOULD BE MAINTAINED.
- WATER MAINS ARE NOT PERMITTED TO BE CONSTRUCTED WITHIN THE ROAD BOX. ROAD CROSSING DESIGN IS TO ACCOUNT FOR THE CONSTRUCTION PHASE OF THE DEVELOPMENT TO PROVIDE THE REQUIRED COVER.
- REFER TO SEQ WS&S D&C CODE TABLE 7.5 AND STANDARD DRAWING SEQ-WAT-1209-1 FOR TRENCHSTOP (GRADE 5-14%) AND BULKHEAD (GRADE 15-29%) DETAILS.

GENERAL NOTES:

- ALL WORK AND MATERIAL SHALL BE IN ACCORDANCE WITH CURRENT SOUTH EAST QUEENSLAND WATER SUPPLY CODE SPECIFICATIONS AND STANDARDS.
- UNLESS SPECIFIED OTHERWISE ALL MATERIALS AND WORK SHALL COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS.
- COVER ON MAINS FROM PERMANENT LEVEL TO BE SHOWN IN SEQ-WAT-1200-2.
- CONDUITS TO BE INSTALLED IN ACCORDANCE WITH THE STANDARD DRAWINGS.
- ALL MATERIALS USED IN THE WORKS SHALL COMPLY WITH THE SEQ-SP'S ACCEPTED PRODUCTS AND MATERIALS LIST OR BE APPROPRIATELY SHOWN, LISTED AND DEFINED IN THE ENGINEERING SUBMISSION SO THAT THE ALTERNATIVE PRODUCT OR MATERIAL CAN BE ASSESSED AND IF APPROPRIATE, APPROVED BY THE SEQ-SP.
- THE CONSTRUCTION OF THE WATER RETICULATION WORK SHOWN ON THIS DRAWING MUST BE SUPERVISED BY AN ENGINEER WHO HAS RPEQ REGISTRATION. WORKS NOT COMPLYING WITH THIS REQUIREMENT WILL NOT BE PERMITTED TO CONNECT TO THE RETICULATION SYSTEM.
- INTERNAL WATER CONDUITS SUBJECT TO SEPARATE PLUMBING APPROVAL.



LIVE WATER MAIN WORKS

| No. | DESCRIPTION | WATER DIA/MAT. | ADJACENT LOT NO. | COVER DEPTH |
|------|---|----------------|------------------|-------------|
| 1(A) | CONTRACTOR TO CONSTRUCT WATERMAIN INCLUDING ALL FITTINGS AND LEAVE 3.0m SHORT OF EXISTING MAIN FOR CONNECTION BY LOGAN CITY COUNCIL. | 100mm DI CL | PATRICK COURT | 600mm |
| 1(B) | CONNECTION TO EXISTING Ø100mm mPVC MAIN BY COUNCIL, COMPLETE INCLUDING SS OFFTAKE CLAMP, 100mm DI CL PN35 FL-FL VALVE AND FL-SOC CONNECTOR IN ACCORDANCE WITH SEQ-WAT-1105.2. | | | |

| | | | |
|---|---|--|---|
| <p>REV REVISION DESCRIPTION DESIGN DRAWN DATE SCALE</p> <p>A ISSUE FOR APPROVAL SO AR 02.06.21 1:250</p> <p>B RESPONSE TO COUNCIL RFI SO SO 02.07.21 1:500</p> <p>C ADDITIONAL CONNECTION FROM GTP2781 ADDED DH DH 02.09.21 </p> | <p>APPROVED DAVID HOLSTEIN (RPEQ 17025)</p> <p>CIVIL 360 ENGINEERING</p> <p>PROJECT MANAGEMENT CIVIL ENGINEERING LAND DEVELOPMENT</p> <p>0406 424 223 / 0423 593 058 info@civil360.com.au</p> | <p>CLIENT STRATEGIC DEVELOPMENTS</p> <p>PROJECT 23 PATRICK COURT 23 PATRICK COURT, WATERFORD WEST LOTS 2 ON RP868324, 3 ON RP186717, 900 ON RP233953, 901 ON RP233970, 902 ON RP231480 & 239 ON SP195519</p> <p>ASSOCIATED CONSULTANTS </p> | <p>DRAWING TITLE WATER RETICULATION PLAN</p> <p>STATUS ISSUE FOR APPROVAL</p> <p>PROJECT No. 2020212</p> <p>DRAWING No. 800</p> <p>REVISION C</p> |
|---|---|--|---|